

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
P. Scheufler No. 3.

SEC. 24 T. 20 R. 12W
CNL NW
440' S 1320' E of NW Cor.

Total Depth. 3340' (3339' Cem. Fl. Level)
Comm. 1-20-41 Comp. 2-10-41
Shot or Treated.
Contractor.
Issued. 5-17-41

County. Barton



CASING:
10 3/4" 245' Cem.
7" 3314' Cem.

Elevation.

Production. Pot. 3000 B. Echo.

Figures Indicate Bottom of Formations. No wtr

surface sand	257
shale & red bed	615
sand & red bed	860
shale & red bed	1260
shale	1402
shale lime	1536
lime & shale	1653
shale lime	1767
lime & shale	1970
lime	2031
shale & lime	2115
lime	2194
lime shale	2611
lime	2653
lime shale	2836
lime	2940
lime & shale	2986
lime	3017
lime & shale	3045
shale	3070
lime & shale	3120
lime	3144
lime shale	3215
shale	3230
lime & shale	3270
lime hrd	3278
lime & shale	3310
shale lime	3316
dolomite	3319
lime hrd	3332
lime	3340
Total Depth.	

Total depth from cement
floor level 3339

Top of Arbuckle lime 3313

Total fillup w/oil 3100' -
Swabbed 157 BO in 1 hr -
could not swab below 1000'
from top of hole
2-12-41 established an Echo.
Pot. of 3000 BO, no wtr

Note: All of above footages
calculated from cement floor
level.