

LLING CONTRACTS A SPECIALTY
OIL LEASES
PRODUCING PROPERTIES
ROYALTIES

J. C. FINDEISS

BOARD OF TRADE BLDG.

WICHITA, KANSAS

PHONE MARKET 2177—OFFICE
PHONE DOUGLAS 3799J—RES.

March 4, 1927.

Cosden Oil & Gas Co.,

Tulsa, Okla.

Gentlemen:

Enclosed I hand you log of the well in Section
22, Township 18-South, Range 3 West, McPherson County, Kansas,
on the Hanson farm to a depth of 1135 feet.

Further continuations of this log will be sent to
you from time to time.

Yours truly,

J.C.Findeiss

LOG OF WELL

LOCATION: The Northeast Corner of the Southeast Quarter of
Section Twenty-two, Township Eighteen South, Range
Three West, McPherson County, Kansas, Hanson Farm,
Well No.1.

Drilling Contractors
Allison & Fitzwilliam
Wichita, Kansas.

Date Commenced
Feb. 7, 1927.

Elevation

Operators
J.C.Findeiss, et al,
Wichita, Kansas.

STRATA	THICKNESS	TOTAL DEPTH	REMARKS
Soil	4	4	
Yellow Clay	136	140	caving at 85'
Red rock	25	165	
Blue shale	55	220	
Red rock	60	280	2-B.W. 220-240
Blue shale	200	480	2-B.W. 275-280
Water sand	5	485	HW
Lime	10	495	caving bad
Blue slate	7	502	
Lime	16	518	
Slate	2	520	
Lime with shale breaks	105	625	
Lime and blue shale	5	630	
Red rock	5	635	
Lime with shale breaks	40	675	
Red rock	10	685	
Lime and shale	60	745	
Red slate	5	750	
Red rock	5	755	
Lime	110	865	
Sandy lime	30	895	2-B.W.-865-895
Hard lime	5	900	
Blue shale	5	905	
Red shale	5	910	
Lime	30	940	
Blue slate	10	950	
Blue shale	5	955	
Sandy lime	10	965	
Lime and shale	20	985	
Lime soft	40	1025	
Slate lite	10	1035	
Blue slate	5	1040	
Lime and shale	55	1095	
Lime	5	1100	
Slate dark	20	1120	
Lime	10	1130	
Black slate	5	1135	



DRILLING CONTRACTS A SPECIALTY
OIL LEASES
PRODUCING PROPERTIES
ROYALTIES

J. C. FINDEISS

BOARD OF TRADE BLDG.

WICHITA, KANSAS

PHONE MARKET 2177—OFFICE
PHONE DOUGLAS 3799J—RES.

March 11, 1927.


Gentlemen:

Enclosed I hand you continuation of the log of the well located in Section 22, Twp. 18-South, Range 3-West, McPherson County, Kansas, from a depth of 1135 feet to 1500 feet.

Further continuation of this log will be mailed to you from time to time.

Yours truly,

J.C.Findeiss

A handwritten signature in dark ink, appearing to read "J.C. Findeiss", written in a cursive style.

CONTINUATION OF LOG.

LOCATION: The Northeast Corner of Southeast Quarter of Section Twenty-two (22),
Township Eighteen (18) South, Range Three (3) West, Worthen County,
Kansas. on Hanson farm, well No.1.

Drilled by
J.C.Findeiss, et al, Wichita, Kansas.

<u>DEPTH</u>	<u>THICKNESS</u>	<u>TOTAL DEPTH</u>	<u>REMARKS</u>
Depth reached on last report		1185	
Blue shale	15	1150	
Red rock	15	1165	
Lime	20	1185	
Slate	10	1195	
Lime	5	1200 1200	
Black slate	5	1205	
Lime	10	1215	
Slate	10	1225	
Slate	5	1230	
Lime	20	1250	
Lime and gray shale	25	1275	
Lime soft	40	1315	
Blue slate	10	1325	
Lime	5	1330	
Lime and blue shale	10	1340	
Gray shale	20	1360	
Blue shale	15	1375	
Red rock	6	1381	
Black slate	4	1385	
Lime	7	1392	
Slate blue	14	1406	
Sand soft	10	1416	S-B.W. 1406-1416'
Shale blue	6	1422	
Red slate	3	1425	
Blue shale	20	1445	
Red rock	10	1455	
Sandy lime	20	1475	H.P.W. 1455-1475
Blue shale	20	1495	
Red rock	5	1500	

DRILLING CONTRACTS A SPECIALTY
OIL LEASES
PRODUCING PROPERTIES
ROYALTIES

J. C. FINDEISS

BOARD OF TRADE BLDG.

WICHITA, KANSAS

PHONE MARKET 2177—OFFICE
PHONE DOUGLAS 3799J—RES.

March 31, 1927.

Gentlemen:

Enclosed I hand you continuation of the log of the well in Section 22, Twp. 18-South, Range 3 West, McPherson County, Kansas, from 1500 feet to 1800 feet.

Further continuation of this log will be mailed you from time to time.

Yours truly,

J. C. Findeiss

J C Findeiss

CONTINUATION OF LOG.

LOCATION: The Northeast Corner of the Southeast Quarter of Section 22, Township
16-South, Range 3-West, McPherson County, Kansas. Hanson Farm Well No.1.

Drilled by
J.C.Findeiss, et al, Wichita, Kansas.

<u>STRATA</u>	<u>THICKNESS</u>	<u>TOTAL DEPTH</u>	<u>REMARKS</u>
Depth reached on last report		1500	
Red rock	10	1510	25 B-W-P-M. caving caving had 1530
Blue shale	45	1555	
Gray lime	30	1585	
Brown slate	40	1625	
Lime	15	1640	
Hard white lime	15	1655	
Soft gray lime	10	1665	
Slate	30	1695	
Lime	10	1705	
Red slate	10	1715	
Lime	20	1735	
Blue shale	25	1760	
Water sand	25	1785	H.P.W. 1760-1785
Lime	5	1790	
Blue shale	5	1795	
Lime	5	1800	

DRILLING CONTRACTS A SPECIALTY
OIL LEASES
PRODUCING PROPERTIES
ROYALTIES

J. C. FINDEISS
BOARD OF TRADE BLDG.
WICHITA, KANSAS

PHONE MARKET 2177—OFFICE
PHONE DOUGLAS 3799J—RES.

June 22, 1927.

Gentlemen:

Enclosed I have you continuation of the log of the well
in Sec. 22, Twp. 18-S, Range 3-West, McPherson County, Kansas, from
2929 feet to 3235 feet.

Further continuation of this log will be mailed you
from time to time.

Yours truly,

J.C.Findeiss

Continuation of the log of the well in the Northeast Corner of the
 Southeast Quarter of Sec. 22, Twp. 18-South, Range 3-West, McPherson
 County, Kansas, Hanson Farm, Well No.1.

Drilled by J.C.Findeiss, et al, Wichita, Kansas.

Strata	Thickness	Total depth	Remarks
Total depth last report		2929	
Lime	11	2940	
Black slate	4	2944	
Lime gray	26	2970	
Blue shale & lime shells	35	3005	
Lime gray	5	3010	
Slate	8	3018	
Lime light	4	3022	
Slate black	16	3038	
Various colored shale	45	3083	
Blue shale	2	3085	
Dark lime	5	3090	
Blue shale	7	3097	
Red rock	3	3100	
Lime	1	3101	
Red rock	14	3115	
Black slate	15	3130	
Blue shale	5	3135	
Chert top Miss. lime	12	3147	little water 3147--2-D.W.-3150
Lime white	23	3170	more water 3160 hole gilling up
White lime hard	28	3198	
Sandy white soft	15	3210	more water 3200
Sandy lime white soft	5	3215	
Lime white hard	70	3285	

