

State Kansas County Decatur

Company Messman-Rinehart Oil Co. Well No. 3

Farm PETRACEK

Survey 40' West of C NW NE

Block No. Sec. 26 Twp. 4S Range 27W

Co-Ord. Elev. 2517 KA

Interestholders

R. F. Seeligson 18.2143%
 A. A. Seeligson, Jr. 18.2143%
 Seeligson Oil Co. 7.5%
 Arthur Watkins 12.5%
 Danal Hotaling 12.5%
 M-R Oil Company 25%
 R & J Gill 6.0714%

Geologist: J. George Klein
 Contractor: Drieling Oil, Inc

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line


Ft. from W. Line

Ft. from E. Line

Date	Depth	Staked location
2/20/72		MIRT
		2 1/2" pipe
		Set 8 5/8" casing at 322'
		w/ 235 lbs cement 3% cement
		plug down to 450 m.
2/28	2990	of Anhydrite 2032 (+48)
2/29	3160	of Anhydrite 2110 (-593)
		Star w/ Petracek #1

Date	Depth	<u>DST #1 3103-62</u>
		Soil: open 1 hr fair below: throughout Rec.
		30' med. w/ specks of oil + 100' slight ocm
		+ 110 med. heavy ocm & 90' ocm mdy water
		RSP 1051 #1/30"
		RSP 1006 #1/30"
		RSP 107, RPP 223
3/1/72		<u>DST #3 3170-82 (Larkin)</u>
		Soil: open 30" weak below
		9" Rec. 30' ocm
		RSP 1113 #1/30", RSP
		926 #1/30" RPP 36-36
		Temp 99°
		<u>Howard 3209 (-685)</u>
		Subsoil tracks #1
		<u>DST #3 3198-3213</u>
		Soil: open 45" weak
		below Rec 60' thin
		mud, 60' w/ mud, 60'
		mdy water
		RSP 757 #1/30", RSP
		757 #1/45" RPP 62-107

State Kans County Decatur
 Company Messman Linhart Well No. 3
 Farm Lehman
 Survey 40' West of C. NW NE
 Block No. _____ Sec. 26 Twp. 4S Range 27W
 Co-Ord. _____ Elev. 2517 KB



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line


Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Sample revealed some barren porosity
		7' good drilling
		Show of oil stain in sample
<u>3/2/27</u>		<u>Lehman 3392 (C-875)</u>
		<u>Lehman 3423 (C-906)</u>
		<u>Lehman 3425 (C-918)</u>
	<u>A & B gms</u>	<u>DST # 4 3427-3465</u>
		<u>Wash below 5" died</u>

Date	Depth	Remarks
		Rec 40' mud
		IBHP 935 [#] /30", FBHP
		889 [#] /30" IFP 45 [#]
		FPF 62 [#] Jump 100'
		"O" zone 3473-79 fair
		porosity spotted stain
	3490	ing
		Well drl "O" & "E" zones
		&lesh. Structure
		thinning 4' Higher
		than #1 Persect
3/3/72		<u>DST #5 3464-3506</u>
		Open 60" weak blow
		Rec 70' mud 40' thin mud
		IBHP 793 [#] /30", FBHP 757 [#] /
		45" FP 54 [#] , PFP 80 [#]
		Jump 100'
		<u>DST #6 3503-3516</u>
		Open 30" strong blow
		through Rec 100' indy
		into 340' into IBHP
		1069 [#] /30" FBHP 1042 [#] /45"
		FP 71 [#] , PFP 178 [#]
		Jump 104
	3535	∅

State Kansas County Decatur
 Company Messner-Lincoln Well No. 3
 Farm Lebrack
 Survey 40' West of C NW NE
 Block No. _____ Sec. 26 Twp. 48 Range 27W
 Co-Ord. _____ Elev. 2517 KB



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		<u>DST #7 3532-84</u>
<u>3/4/72</u>		<u>Well open 1 hr week</u>
		<u>blow thru out test</u>
		<u>Rec 200' mud 125'</u>
		<u>mdy. to 1 BHP 935#/35"</u>
		<u>1 RP 707, ROP 205,</u>
		<u>2 BHP 917#/45" Imp</u>
		<u>100'</u>
		<u>DST #8 3585-3625</u>
		<u>Well open 30' week</u>

