



P. O. BOX 1599
WICHITA, KANSAS 67201

Company Icer Addis Lease & Well No. Hollis #1
Elevation 1373 Ground Level Formation Viola Effective Pay - Ft. Ticket No. 21427
Date 4-20-75 Sec. 20 Twp. 13S Range 10W County Greenwood State Kansas
Test Approved by Donald J. Malone Western Representative Forrest Funnell
Formation Test No. 1 O.K. ☒ Misrun ☐ Interval Tested From 2878' to 2885' Total Depth 2885'
Size Main Hole 7 7/8 Bar Hole ☐ Conv. ☐ B.T. ☒ Damaged ☐ Yes ☒ No Conv. ☒ B.T. ☐ Damaged ☐ Yes ☒ No
Top Packer Depth 2873 Ft. Size 5 1/2 Bottom Packer Depth 2878 Ft. Size 5 1/2
Straddle ☐ Conv. ☐ B.T. ☐ Damaged ☐ Yes ☒ No Packer Depth 2 Ft. Size -
Tool Size 4 1/2 OD Tool Joint Size 3 1/2 IF Anchor Length 7 Ft. Size 4 1/2 OD Surface Choke Size 3/4 In. Bottom Choke Size 3/4 In.
RECORDERS Depth 2866 AP Ft. Clock No. 10168 Depth 2881 Ft. Clock No. 10167
Top Make Kuster Cap. 4250 No. 1051 Inside ☐ Outside ☒ Bottom Make Kuster Cap. 4200 No. 3354 Inside ☐ Outside ☒
Below Straddle: Depth - Rec. No. - Clock No. - Inside ☐ Outside ☒ Depth - Ft. Rec. No. - Clock No. - Inside ☐ Outside ☒
Time Set Packer 10:27A M
Tool Open I.F.P. From 10:30AM to 11:00AM - Hr. 30 Min. From (B) 24 P.S.I. To (C) 861 P.S.I.
Tool Closed I.C.I.P. From 11:00AM to 11:30AM - Hr. 30 Min (D) 971 P.S.I.
Tool Open F.F.P. From 11:30A M. to 12:00AM - Hr. 30 Min. From (E) 905 P.S.I. To (F) 979 P.S.I.
Tool Closed F.C.I.P. From 12:00M to 12:30PM - Hr. 30 Min. (G) 979 P.S.I.
Initial Hydrostatic Pressure (A) 1408 P.S.I. Final Hydrostatic Pressure (H) 1398 P.S.I. Maximum Temp. 122

INFORMATION

BLOW Strong 15" blow decreasing to a 2" blow throughout test.

Did Well Flow ☒ Yes ☒ No Recovery Total Ft. 2284' muddy water.

Reversed Out ☒ Yes ☐ No Mud Type Chemical Viscosity 45 Weight 9.5 Water Loss 10.4 cc. Chlorides 800 PPM

EXTRA EQUIPMENT: Type Circ. Sub. pin Safety Joint ☐ Jars: Size - In. Make - Ser. No. -

Dual Packer ☒ Yes Did Packers Hold? ☒ Yes Did Tool Plug? ☒ No Where? -

DRILLING CONTRACTOR B & N Drilling Co. Length Drill Pipe? 2728 Ft. I.D. Drill Pipe 2.7 In. Tool Joint Size 3 1/2 IF In.

Length Weight Pipe - Ft. I.D. Weight Pipe - In. Tool Joint Size - In. Length Drill Collars 120 Ft. I.D. Drill Collars 2 1/2 In.

Tool Joint Size 3 1/2 IF In. Length D.S.T. Tool 31 Ft.

Remarks:

WESTERN TESTING CO., INC.

Pressure Data

Date **4-20-75**

Test Ticket No. **21427**

Recorder No. **1051** Capacity **4250** Location **2866** Ft.

Clock No. **10168** Elevation **1373 Ground Level** Well Temperature **122** °F

Point	Pressure		Time Given	Time Computed
A. Initial Hydrostatic Mud	1408 P.S.I.	Open Tool	10:27 A M	
B First Initial Flow Pressure	24 P.S.I.	First Flow Pressure	30 Mins.	30 Mins.
C First Final Flow Pressure	861 P.S.I.	Initial Closed-in Pressure	30 Mins.	27 Mins.
D Initial Closed-in Pressure	971 P.S.I.	Second Flow Pressure	30 Mins.	30 Mins.
E Second Initial Flow Pressure	905 P.S.I.	Final Closed-in Pressure	30 Mins.	30 Mins.
F Second Final Flow Pressure	979 P.S.I.			
G Final Closed-in Pressure	979 P.S.I.			
H Final Hydrostatic Mud	1398 P.S.I.			

PRESSURE BREAKDOWN

First Flow Pressure		Initial Shut-In		Second Flow Pressure		Final Shut-In	
Breakdown: 6 Inc.		Breakdown: 9 Inc.		Breakdown: 6 Inc.		Breakdown: 10 Inc.	
of 5 mins. and a		of 3 mins. and a		of 5 mins. and a		of 3 mins. and a	
final inc. of 0 Min.		final inc. of 0 Min.		final inc. of 0 Min.		final inc. of 0 Min.	
Point Mins.	Press.	Point Minutes	Press.	Point Minutes	Press.	Point Minutes	Press.
P 1 0	24	0	861	0	905	0	979
P 2 5	200	3	966	5	917	3	979
P 3 10	405	6	970	10	949	6	979
P 4 15	549	9	971	15	967	9	979
P 5 20	678	12	971	20	977	12	979
P 6 25	781	15	971	25	978	15	979
P 7 30	861	18	971	30	979	18	979
P 8		21	971			21	979
P 9		24	971			24	979
P10		27	971			27	979
P11						30	979
P12							
P13							
P14							
P15							
P16							
P17							
P18							
P19							
P20							