

WESTERN TESTING COMPANY INC.
SUBSURFACE PRESSURE SURVEY

DATE: 9/26/84
CUSTOMER: D N B DRILLING INC.
WELL: 1
ELEVATION (KB): 1305
SECTION: 3
RANGE: 3E
GAUGE SN #3474

TEST: 1
FORMATION: SIMPSON
TOWNSHIP: 28S
COUNTY: BUTLER
RANGE: 3000

TICKET #6279
LEASE: TRABUE
GEOLOGIST: JOHNSON
STATE: KANSAS
CLOCK: 12

INTERVAL TEST FROM: 3031 FT TO: 3046 FT TOTAL DEPTH: 3046 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 3031 FT SIZE: 6 3/4 IN PACKER DEPTH: 3026 FT SIZE: 6 3/4 IN
PACKER DEPTH: FT SIZE: IN PACKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WHITE & ELLIS
MUD TYPE: CHEMICAL VISCOSITY: 40
WEIGHT: 9.4 WATER LOSS (CC): 8
CHLORIDES (P.P.M.): 3000
JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? NO REVERSED OUT?
DRILL COLLAR LENGTH: 300 FT I.D.: 2.25 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 2711 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 20 FT TOOL SIZE: 5 1/2 IN
ANCHOR LENGTH: 15 FT SIZE: 5 1/2 IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 XH IN

BLOW: GOOD BLOW THROUGHOUT TEST.

RECOVERED: 820 FT OF: SALT WATER
RECOVERED: FT OF: CHLORIDES 20000 PPM
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:


REMARKS:

TIME SET PACKER(S): 1:10 A.M. TIME STARTED OFF BOTTOM:
WELL TEMPERATURE: 109 °F
INITIAL HYDROSTATIC PRESSURE: (A) 1530 PSI
INITIAL FLOW PERIOD MIN: 30 (B) 143 PSI TO (C) 347 PSI
INITIAL CLOSED IN PERIOD MIN: 51 (D) 1043 PSI
FINAL FLOW PERIOD MIN: 30 (E) 373 PSI TO (F) 511 PSI
FINAL CLOSED IN PERIOD MIN: 36 (G) 1024 PSI
FINAL HYDROSTATIC PRESSURE (H) 1489 PSI

TKT # 6279

3474
DST #

I



TKT # 6279

O

