

SINCLAIR OIL & GAS COMPANY

SCHOUMACHER FARM  
Sec. 13 - 25-S. - 4-East.

Well #1

			Casing record:	Commenced drilling June 10th., 1917
135'	1 1/2"	70#	Casing.	Completed drilling ????
885'	1 1/2"	50#	Casing.	By Richard Drilling Company,
1625'	10"	35#	Casing.	By C. C. Gregory Drilling Contractor.
2509'	5 3/16"	17#	Casing.	By Gabler & Brannon Rig Contractor.
2270'	6 5/8"	20#	Casing.	

Formation	FORMATION RECORD:		Thickness	Remarks.
	From	To		
Soil	0	15	15	
Sand	15	40	25	
Blue Mud	40	45	5	
Red Rock	45	70	25	
Blue-Mud	70	90	20	
Lime	90	95	5	
Sand	95	110	15	Water at 110'.
Red Rock	110	130	20	
Lime	130	160	30	
White-Slate	160	200	40	
Lime	200	225	25	
White-Slate	225	275	50	
Blue-Mud	275	295	20	
Lime	295	310	15	
Blue-Mud	310	320	10	
Red Rock	320	340	20	
Lime	340	375	35	
Blue-Mud	375	390	15	
Lime	390	400	10	
White-Slate	400	410	10	
Lime	410	420	20	
Black-Shale	420	440	20	
White-Slate	440	450	10	
Red Rock	450	460	10	
Lime	460	470	10	
White-Slate	470	480	10	
Lime	480	490	10	
White-Slate	490	520	30	
Red Rock	520	530	10	
Lime	530	585	55	
White-Slate	585	610	25	
Lime	610	625	15	
Black-Slate	625	680	55	
Lime	680	705	25	
White-Slate	705	740	35	
Black-Slate	740	750	10	
Sand	750	765	15	Water.
Black-Slate	765	775	10	
Red Rock	775	780	5	
Sand	780	790	10	
Red Rock	790	820	30	
Lime	820	825	5	
Blue-Mud	825	865	40	
Sand	865	885	20	Water.
Red Rock	885	890	5	
White-Slate	890	915	5	
White-Slate	915	925	10	
White-Slate	925	960	35	
Lime	960	1010	50	
White-Slate	1010	1040	30	
Lime	1040	1080	40	
White-Slate	1080	1120	40	
Black-Shale	1120	1135	15	
Sand	1135	1145	10	
Black-Slate	1145	1185	40	
White-Slate	1185	1200	15	
Lime	1200	1220	20	
Black-Shale	1220	1245	25	
Lime	1245	1275	30	
Shale	1275	1310	35	

Lime	1310	1340	30	
Black-Shale	1340	1360	20	
Shale	1360	1380	20	
Lime	1380	1410	30	
Black-Shale	1410	1420	10	
Lime	1420	1455	35	
Black-Shale	1455	1460	5	
Sand	1460	1465	5	Water
Black-Shale	1465	1470	5	
Sand	1470	1480	10	Water
Black-Shale	1480	1495	15	
Lime	1495	1570	75	
Black-Shale	1570	1625	55	
Lime	1625	1665	40	
Slate	1665	1685	20	
Lime	1685	1710	25	
Slate	1710	1750	40	
Sand	1750	1780	30	Water
Slate	1780	1820	40	
Lime-Slate	1820	1835	15	
Slate	1820	1855	20	
Lime	1855	1895	40	
Lime	1895	1905	10	
Slate	1905	1940	35	
Sand & Lime	1940	2115	175	Water at 2050'.
Slate	2115	2270	155	
Lime	2270	2295	25	
Slate	2295	2300	5	
Lime & Sand	2300	2380	80	Water at 2324'.
Black-Shale	2380	2385	5	
Lime	2385	2390	5	
Black-Shale	2390	2400	10	
Lime	2400	2435	35	
Black-Shale	2435	2509	74	
Lime	2509	2514	5	
Sand	2514	2538	24	Water at 2530'.
Blue-Shale	2538	2547	9	
Lime	2547	2555	8	
Black-Shale	2555	2596	41	
Lime	2596	2606	10	
Black-Shale	2606	2610	4	
Lime	2610	2618	8	
Black-Shale	2618	2632	14	
Lime	2632	2647	15	
Black-Shale	2647	2668	21	
Red Rock	2668	2680	12	
Blue Shale	2680			Still drilling.