

LOG OF THE JENKINS WELL # 1.

Located in Sec. 30- Twp.-17-R.15-E. Osage County; Kansas. Contractor; J. E. Goons.
Commenced Drilling, July, 3rd. 1927.-Completed Drilling, Sept. 12th. 1927.
Drilled for Roxana Petroleum Corp. Cooden Oil Co. S.C. McBride, Et. Al.
Drillers; Wm. Reimer, J.W. Johnson, J.L. Henderson.

FIGURES GIVEN INDICATE BOTTOM OF FORMATION.

Soil	5- Ft.	Shale - Blue.	Set, 2151-Ft. 6-5/8"	2155-Ft.
Line	55	" - Brown		2177
Shale	65	Line - White		2180
Line	70	Sand - WILCOX.		2183
Shale	80	Line - Light		2186
Line	100	Line-Hard-Sandy.	TOTAL DEPTH.	2204
Shale	125			
Line	135			
Shale	150			
Line	160			
Shale	185			
Line	195			
Shale	205			
Line	220			
Shale	225			
Line	230			
Shale	255			
Line	265			
Shale	280			
Line	310			
Shale	325			
Line	355			
Shale	470			
Line	475			
Sand	505			
Shale	530			
Shale-sandy	600			
Sand	650			
Line	675			
Shale	678			
Line	735			
Shale	790			
Line	800			
Shale	820			
Line	875			
Shale	885			
Line	895			
Shale	905			
Red Rock	910			
Shale	915			
Line	940			
Shale	960			
Line	1035			
Shale	1190			
Line	1215			
Shale	1245			
Line	1255			
Shale	1260			
Line	1265			
Shale	1285			
Line	1290			
Shale	1350			
Sand-Brown	1365			
Shale	1480			
" - Sandy	1495			
" - Black.- Cave	1525			
" - Black	1530			
" - Black	1640			
Sand - Brown	1707			
Line- White-MISSISSIPPI.	1712			
" - Brown	1722			
Sand-H.F. Water-Set, 1749-ft. 8 1/2"	1747			
Line-White	1749			
Shale- Black	1775			
Line- White	1777			
Shale- "	1780			
Line - "	1783			
" - Brown	1855			
" - Gray	1880			
" - White	1995			
" - Blue	2025			
" - Brown	2050			
	2100			

CASING RECORD.

12 1/2"	21-Ft.
10 "	755
8 1/2"	1749
6-5/8"	2131

Independence, Kansas, Sept. 14th. 1927.

I hereby certify the foregoing to be a true and correct copy of the log of the Jenkins well # 1- Drilled by me in Sec.-30-Twp.-17-R.15-E. Osage County, Kansas.

J. E. Goons

→ Samples show this lime very cherty - It is siliceous lime and I recommend paying off on the well

A. L. Beckley

*OK. to pay
Goons & Co.*