

CHENEY TESTING COMPANY

P. O. BOX 3

HILL CITY, KANSAS 67642

DRILL-STEM TEST DATA

Company	Abercrombie Drlg. Inc.	Test No.	1
Well Name & Number	Splitter #1	Zone Tested	Cherokee
Company Address	Wichita, Kan.	Date	12-3-78
Comp. Rep.	Vic Reiserer	Tester	Orman Bell
Contractor	Co. Tools	Elevation	2819 K.B.
Location: Sec. 11 Twp. 19 Rge. 29W Co. Lane State Kan.		Est. Feet of Pay	

Recorder No. 6730 Type AK-1 Range 4200 PSI

Recorder Depth 4635

(A) Initial Hydrostatic Mud 2280 PSI

(B) First Initial Flow Pressure 10 PSI

(C) First Final Flow Pressure 10 PSI

(D) Initial Closed-in Pressure 53 PSI

(E) Second Initial Flow Pressure 10 PSI

(F) Second Final Flow Pressure 10 PSI

(G) Final Closed-in Pressure 32 PSI

(H) Final Hydrostatic Mud 2270 PSI

Temperature 116

Mud Weight 9.2 Viscosity 45

Fluid Loss 13.6 cc

Interval Tested 4583-4638

Anchor Length 55

Top Packer Depth 4578

Bottom Packer Depth 4583

Total Depth 4638

Drill Pipe Size 4 1/2 F.H.

Wt. Pipe I. D. 2.7 Ft. Run 505

Recovery—Total Feet 50

Recovered 50 Feet Of Mud

Recovered Feet Of

Recovered Feet Of

Recovered Feet Of

Extra Equipment None

Recorder No. 10216 Type AK-1 Range 4200 PSI

Recorder Depth 4632

Tool Open Before I. S. I. 30 Mins.

Initial Shut-in 45 Mins.

Flow Period 60 Mins.

Final Shut-in 45 Mins.

Surface Choke Size 1"

Bottom Choke Size 3/4"

Main Hole Size 7 7/8"

Rubber Size 6 3/4"

Tool Open @ 5:45 P.M.

Blow Very Weak. Blow died in 20 min.

Remarks on first opening

Dead on second open, flushed tool.

Drill Collar I. D. 2.7 Ft. Run 325

Price of Job \$440.00

K# 1478

