

Mid-Kansas Oil & Gas Company
 No. 2 Myers farm, Sec. 3-28-42,
 Butler County, Kansas.
 Brady Brothers, Contractors.

Producing well.

Lime	0	25
Lime & Slate	25	75
Lime	75	95
Lime & Slate	95	145
Lime	155	170
Red rock	170	176
Black slate	176	192
Lime	192	202
Slate	202	214
Lime	214	235
Slate	235	289
White slate	289	340
Lime	340	360
4 bailers water		
Slate	360	425
Lime	425	440
Slate	440	490
Sand-water	490	496
6 bailers water per hour.		
Slate	496	510
Lime	510	522
Slate	522	592
Red rock	592	598
Slate	598	620
Lime	620	625
Slate	625	735
Lime	735	740
Slate-black	740	760
Lime	760	820
Slate	820	834
Slate-black	834	864
Lime	864	870
Slate	870	905
Slate	905	950
Sandwater	950	970
4 bailers water per hour.		
Lime	970	1055
Slate	1055	1085
Lime	1085	1140
Slate	1140	1155
Lime	1155	1185
Slate	1185	1195
Lime-hard	1195	1250
Slate	1250	1260
Lime	1260	1330
Water sand	1330	1365
Hole full of water.		
Lime	1365	1380
Slate	1380	1385
Lime	1385	1390
Slate	1390	1445
Sand-gas	1445	1455
Lime	1455	1465
Sand	1465	1470
little gas		
Lime	1470	1490
Slate	1490	1505
Lime	1505	1510
Slate	1510	1575
Lime	1575	1595
Slate	1595	1670
Lime	1670	1680
Lime	1680	1800
Sand-water	1800	1810

Lime	1810	1905
Lime-hard	1905	1925
Slate	1925	1965
Lime	1965	1975
Slate	1975	2025
Lime	2025	2030
Slate	2030	2040
Lime	2040	2175
Lime-hard	2175	2210
Slate	2210	2215
Lime	2215	2235
Slate	2235	2240
Lime	2240	2260
Lime-hard	2260	2280
Slate	2280	2315
Hole full of water		
Water sand	2330	2340
Lime	2340	2351
Lime	2351	2360
Slate	2360	2376
Lime	2376	2390
Slate	2390	2400
Lime	2400	2405
Slate	2405	2420
Lime	2420	2435
Slate	2435	2500
Hole caving.		
Black slate	2500	2520
Lime	2520	2525
Slate	2525	2540
Red rock	2540	2550
Slate	2550	2565
Slate	2565	2575
Lime	2575	2580
Par. Iron	2580	2585
White slate	2585	2590
Blue slate	2590	2595
Sand	2595	2605
Slate	2605	2610
Lime	2610	2620
Whiti show of oil.		
Sand	2620	2632
Hole full of water.		
Lime	2632	2640
Lime	2640	2650
Sand	2650	2655
Dry & abandoned at		2655

CASING RECORD

12 1/2"	43'-cemented
10"	797
8 1/2"	1361
6 5/8"	2351
5 5/16"	2632-all pulled.
6"	reamed from 2330 to 2351.
5"	reamed from 2563 to 2634 ft.