

EARLY

1

4

MUSGROVE PETROLEUM CORPORATION

KANSAS

LEASE

WELL NO.

TEST NO.

COMPANY

DISTRICT



OIL WELL CEMENTING CO.

LOCATION	4-33-11		Date	6-23-54	
FIELD	Wildcat		Ticket No.	71662	
COUNTY	Barber		HOWCO DISTRICT	Pratt	
STATE	Kansas		Kind of Job	Open Hole	
CONTRACTOR	Musgrove Pet. Corp.		Price	\$215.00	
MUD DATA			Second Packer Assembly	-	
Kind	Starch		Safety Joint	-	
Weight	10.2 lbs.-gal.	Formation Tested	Extra Folder Charge	-	
Viscosity	44 Sec.	Size Drill Pipe	Jars	-	
Filter Loss	17 c. c. Filter Cake 2/32 in.	Size Bottom Choke			
Est. Gauge Depth Temp.	125 F°	Size Hook Wall Packer			
Time Tool Open	1 Hour	Size D. E. Wall Packer			
Time Closed In.	20 Minutes	Size & Length Anchor			
Depth BT. Gauge	4852' Ft.	PRD Device No.			
BT. P.R.D. No.	311	Blanked Off	Yes		
12 Hr. Clock No.	1794	REMARKS:			
Pressure Readings		Tool opened with a medium blow throughout the			
Initial Hydro Mud Pressure	2633 p.s.i.	test. Recovered 700' of salt water.			
Initial Flow Pres.	34 p.s.i.				
Final Flow Pres.	353 p.s.i.				
Closed in Pres.	1836 p.s.i.				
Final Hydro Mud Pressure	2603 p.s.i.				
Amount of Cushion		None		All depths measured from 1481' Derrick Floor	
				No. Folders Reproduced 5	

11-558-11

TIME

PRESSURE

71662

Each Horizontal Line Equal to 1000 p.s.i.