

Company CASSODAY OIL CORP.
Farm Kollman No. 1.

SEC. 5 T. 12 R. 15 W
S E NW NW


15-167-87263-0001

DEEPENING RECORD

Total Depth. 3105'
Comm 8-28-25
Shot or Treated.
Contractor.
Issued. 12-7-46

Comp. 10-20-25

County. Russell
KANSAS



CASING:
20" 137' 10" 1405'
15 1/2" 504' 8 1/4" 2284'
12 1/2" 760' 65/8" 2547'

Elevation. _____

Production. 40 B.

Figures Indicate Bottom of Formations.

shale blue 3BW	54	slate	2284
wtr sand	66	lime	2288
shale	140	slate	2314
wtr sand HFW	152	shale blue	2465
shale	200	lime (sh oil 2465)	2470
slate	364	slate (2BW 2475)	2476
shale	394	lime	2480
red rock	404	shale	2495
lime	412	lime	2517
sand red	440	shale	2525
lime	463	lime, sh oil	2530
red sand & rock	740	shale	2547
slate wh	755	lime	2551
lime gy	795	slate	2559
red rock	880	lime	2650
shale brwn	940	slate	2660
red rock	1028	lime	2760
slate	1068	shale	2775
lime	1126	lime	2793
shale brwn	1168	red rock	2799
lime	1330	lime	2800
shale	1350	slate	2804
lime	1355	lime	2818
slate	1365	slate	2820
slate & shells	1405	lime brkn	2829
shale brwn	1425	lime wh	2833 6" pay
lime	1450	Total Depth.	
slate	1480		
d rock	1500	Dodge pay	2780
lime	1530	Oswald pay	2811
slate	1560	Oswald pay	2816
lime	1615	Oswald pay	2833-6"
slate brwn	1640		
lime	1660	sh oil 2775-80 filled	
slate	1686	up to 2000 tested 36.5	
lime, sh of gas	1712	gravity	
rock 1760-1705?			
lime	1775	DEEPENING RECORD:	
slate brwn	1785	Comm. 2-17-26	
rock	1813	Comp. 3-24-26	
lime	1818	Prod. 15 BPD,	
slate	1828	40 B. before deepening	
rock	1832	lime	2862
	1843	lime & shale, swbd	
rock	1970	23 B. 24 hrs	2864
e brwn	1980	lime	2872
	2000	lime & slate	2878
rock	2058	lime brkn	2887
e blue &		lime	2893
shells	2065	lime wh	2898
lime	2077	gas show 2890-93, 2 1/2 BW	
rock	2083	lime	2911
lime	2108	lime hd	2926
shale blue	2175	lime	2947
slate	2195	Total Depth.	
lime	2205		
shale blue	2210	P. B. 2875	
slate blk	2235		
sand (2BW 2240)	2245		

DEEPENING RECORD

Aylward Prod. Co. &
E.R. Corn
Contr-Aylward Prod. Co.
Comm. 2-1-46
Comp. 4-29-46
Est. 200 B.

lime	2950
lime & shale cavings	2955
shale	2958
lime brkn	2964
lime hd	2966
lime	2971
red rock	2976
lime	2992
red rock	2995
lime	3005
red rock cave	3009
lime	3059
lime hd	3065
lime & shale	3075
lime	3091
shale	3092
lime	3098
conglomerate	3100
sand	3105
Total Depth.	

Ran 356' of 4" liner
Hole filled from 1035
to 1235 in 1 hr
Hole filled to 1520' in
3 1/2 hrs