


FORMATION

TEST

REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

WESTERN TESTING CO. INC.  
SUBSURFACE PRESSURE SURVEY

DATE: 1/6/84  
CUSTOMER: E.H. WOODS JR.  
WELL: 7  
ELEVATION (KB): 0  
SECTION: 34  
RANGE: 9W  
GAUGE SN #13402

TEST: 1  
FORMATION: MISSISSIPPI  
TOWNSHIP: 31S  
COUNTY: HARPER  
RANGE: 4025

TICKET #3089  
LEASE: "A" DUSENBURY  
GEOLOGIST: PAULSEN  
STATE: KANSAS  
CLOCK: 12

INTERVAL TEST FROM: 4408 FT TO: 4415 FT TOTAL DEPTH: 4415 FT  
DEPTH OF SELECTIVE ZONE: FT  
PACKER DEPTH: 4403 FT SIZE: 6 3/4 IN PAKER DEPTH: 4408 FT SIZE: 6 3/4 IN  
PACKER DEPTH: FT SIZE: IN PAKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: GRAVES DRLG  
MUD TYPE: CHEMICAL VISCOSITY: 40  
WEIGHT: 9.2 WATER LOSS (CC): 31.2  
CHLORIDES (P.P.M.): 15500  
JARS - MAKE: SERIAL NUMBER:  
DID WELL FLOW? NO REVERSED OUT? NO  
DRILL COLLAR LENGTH: 120 FT I.D.: 2.2 IN  
WEIGHT PIPE LENGTH: FT I.D.: IN  
DRILL PIPE LENGTH: 4263 FT I.D.: 3.8 IN  
TEST TOOL LENGTH: 25 FT TOOL SIZE: 5 1/2 OD IN  
ANCHOR LENGTH: 7 FT SIZE: 5 1/2 OD IN  
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN  
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 XH IN

BLOW: STRONG BLOW THROUGHOUT TEST.  
GAS TO SURFACE IN 25 MINUTES ON FINAL FLOW.  
SEE ATTACHED SHEET FOR GAS MEASUREMENTS.

RECOVERED: 90 FT OF: GAS CUT MUD.  
RECOVERED: FT OF:  
RECOVERED: FT OF:  
RECOVERED: FT OF:  
RECOVERED: FT OF:  
RECOVERED: FT OF:  
RECOVERED: FT OF:  
RECOVERED: FT OF:  
RECOVERED: FT OF:

REMARKS:

TIME SET PACKER(S): 5:55 AM TIME STARTED OFF BOTTOM: 8:55 AM  
WELL TEMPERATURE: 120 °F  
INITIAL HYDROSTATIC PRESSURE: (A) 2256 PSI  
INITIAL FLOW PERIOD MIN: 30 (B) 69 PSI TO (C) 47 PSI  
INITIAL CLOSED IN PERIOD MIN: 30 (D) 1206 PSI  
FINAL FLOW PERIOD MIN: 60 (E) 63 PSI TO (F) 44 PSI  
FINAL CLOSED IN PERIOD MIN: 60 (G) 1281 PSI  
FINAL HYDROSTATIC PRESSURE (H) 2256 PSI



WESTERN TESTING CO. INC.  
GAS FLOW REPORT

DATE: 1/6/84  
CUSTOMER: E.H. WOODS JR.  
WELL: 7  
ELEVATION (KB): 0  
SECTION: 34  
RANGE: 9W  
GAUGE SN #13402

TEST: 1  
FORMATION: MISSISSIPPI  
TOWNSHIP: 31S  
COUNTY: HARPER  
RANGE: 4025

TICKET #3089  
LEASE: "A" DUSENBURY  
GEOLOGIST: PAULSEN  
STATE: KANSAS  
CLOCK: 12

TIME GAUGE (MIN)	TESTER TYPE	ORIFICE SIZE	PRESSURE (PSI)	FLOW DESCRIPTION
---------------------	-------------	-----------------	-------------------	------------------

PRE FLOW

SECOND FLOW


35	MERLA	1/2	5"OF WTR	14100 CFPD
45			6"OF WTR	15400 CFPD
55			6"OF WTR	15400 CFPD
60			6"OF WTR	15400 CFPD

GAS BOTTLE SN #:  
DATE BOTTLE FILLED:  
DATE TO BE INVOICED:

13402  
D57 #1

ICE # 3089

I



1559  
DST 2/

ICE# 3089

0

