

DRILLERS' WELL LOG

22-12-15W
SE-NE-NE

DATE COMMENCED: October 2, 1974
DATE COMPLETED: October 10, 1974

Louis M. Mai
STEINERT # 1
SE NE NE 22-12-15W
Sec. 21-~~T12-R15W~~ (K6S-DRL)
Russell County, Kansas


KANSAS GEOLOGICAL SOCIETY.
Wichita, Kansas

ELEVATION: 1780 K.B.

- 0 - 80' Post Rock - Clay
- 80 - 286' Blue Shale - Sand Streaks
- 286 - 530' Shale - Sand Streaks
- 530 - 847' Red Bed
- 847 - 887' Anhydrite
- 887 - 2353' Shale & Lime Streaks
- 2353 - 2682' Lime & Shale
- 2682 - 2900' Lime
- 2900 - 2904' Shale
- 2904 - 2919' Lime & Shale
- 2919 - 3203' Lime
- 3203 - 3230' Lime - Shale
- 3230 - 3240' Lime
- 3240' RTD

FORMATION TOPS

Anhydrite	847
Grand Haven	2353
Dover	2386
Tarkio Lime	2427
Elmont	2485
Topeka	2682
Heebner	2900
Toronoto	2919
Lansing	2949
Base K.C.	3203
Marmonton	3230
RTD	3240



SURFACE CASING: Set used
2 1/2", 8-5/8" pipe at 283'
with 175 sacks common, 2% Gel
3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Wayne Dobbs of lawful age does swear and state that the facts and statements
herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 11 day of October 1974.

My Comm. Expires:
April 11, 1978

Clarence M. Hague
Notary Public