

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


28-12-15W

Company- RUDY HERMAN OIL OPERATIONS
Farm- Keeney "A" No. 1

SEC. 28 T. 12 R. 15W
SW SW NW

Total Depth. 3320'
Comm. 11-29-58 Comp. 12-10-58
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 1-28-61

County Russell
KANSAS



CASING:
8 5/8" 211' cem w/150 sx.
5 1/2" 3319' cem w/125 sx.

Elevation. 1850' DF

Production. 121 BOPD

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

2733-2737 Occasional rich brown Oil stain
in buff sucrose limestone.

2927-2930 Rare lgt brn spotted oil stain
in buff crystalline limestone

2975-2980 Scattered rich brown oil stain
in buff sucrose limestone

3005-3010 Scattered lgt brn rich oil
staining in buff crystalline & sucrose
limestone

3031-3036 Rare lgt brn oil stain in buff
crystalline limestone

3049-3053 Rare lgt brn oil stain in buff
crystalline & oolitic limestone

3093-3096 Rare lgt brn oil stain in buff
crystalline limestone

3101-3104 white oolitic limestone carrying
rare traces of spotted lgt brn oil stain.

3214-3218 Rare lgt brn oil stain in buff
crystalline & matted oolitic limestone

3261-3263 Rare spotted lgt brn oil stain
in dense buff crystalline limestone

3279-3284 Soft white chalky to medium
crystalline dolomite & carried scattered
lgt brn oil stain.

3284-3292 white fine to medium crystalline
dolomite carrying scattered lgt brn oil
stain.

3292-3300 Same as the 3284-3292 with a
definite increase in staining, saturation,
and porosity.

3300-3310 dense fine crystalline dolomite
and medium to coarse crystalline white
dolomite. Scattered lgt brn oil stain &
saturation.

3310-3320 White coarse crystalline dolomite
carrying scattered rich lgt to dark brown
oil stain. Good saturation.

Rotary Total Depth 3320

DST #1 2983-3020', op 1 hr, weak blow
steady for 1 hr, rec. 220' gas in drill
pipe & 80' oil & gas cut mud. IFP 100#,
FFP 110#, BHP 390#/30 mins.

DST #2 3020-3040', op 1 hr, strong blow
thruout test, gas to surf. in 1 hr,
245' clean gassy oil, IFP 0#, FFP 0#,
BHP 440#/30 mins.

DST #3 3040-3055', op 1 hr, fair blow
for 1 hr, rec. 155' of gas in drill pipe.
25' of slightly oil & gas cut mud.
IFP 0#, FFP 0#, BHP 0#/30 mins.

DST #4 3273-3300', op 1 hr, strong blow
thruout test, rec. 660' gassy oil,
IFP 0#, FFP 70#, BHP 740#/30 mins.

DST #5 3300-3310', op 1 hr, good blow
thruout test, rec. 470' clean gassy oil.
IFP 0#, ffp 170#, BHP 790#/30 mins.

DST #6 3310-3320', op 1 hr, fair blow
for 1 hr, rec. 150' muddy water
no show oil. IFP 0#, FFP 0#,
BHP 940#/30 mins.

TOPS: SAMPLE
Anhydrite (Driller) 906
Topeka 2731
Heebner 2952
Toronto 2971
Lansing-Kansas City 3001
Reworked Arbuckle 3279
Solid Arbuckle 3284