

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


28-12-15W

Company- RUDY HERMAN OIL OPERATIONS
Farm- Keeney "A" No. 3

SEC. 28 T. 12 R. 15W
SW NW NW

Total Depth. 3330'
Comm. 3-3-59 Comp. 3-13-59
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 1-28-61

County Russell
KANSAS



CASING:
8 5/8" 935' cem w/450 sx.
5 1/2" 3329' cem w/150 sx.

Elevation. 1867' DF

Production. 131 BOPD

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

TOPS: SAMPLE

2750-2754 Scattered rich brn oil stain
in buff sucrose limestone.

Anhydrite (Driller)	923
Topeka	2747
Heabner	2968
Toronto	2986
Lansing-Kansas City	3017
Conglomerate	3289

2845-2847 rare spotted lgt brn oil stain
in dense buff crystalline limestone

2938-2941 buff crystalline limestone carrying
rare trace of lgt brn oil stain.

2988-2992 scattered lgt brn oil stain in
buff crystalline & sucrose limestone.

3023-3028 scattered lgt brn oil stain in
buff crystalline & sucrose limestone.

3047-3054 occasional lgt brn oil stain in
buff crystalline limestone

3063-3068 scattered lgt brn oil stain in
buff crystalline limestone

3098-3091 very rare trace of lgt brn oil
stain in buff crystalline limestone

3110-3113 very rare lgt brn oil stain in
buff to white oolitic limestone

3113-3117 rare trace of lgt brn stain in
buff to white oolitic limestone

3156-3160 rare lgt brn oil stain in dense
white crystalline limestone

3178-3181 rare trace of lgt brn oil stain
in buff to white crystalline & chalky
limestone

3234-3237 dense buff to white crystalline
limestone carrying rare very spotted lgt
brn oil stain.

3280-3286 scattered rich drk brn to black
oil stain in buff to brown fossiliferous
limestone

3289-3330 Vari-colored chert & shales,
No show of oil or gas.
Rotary Total Depth 3330

DST #1 3019-3057 op 1 hr, strong blow
1 hr, rec. 960' gas in pipe, 60' slightly
oil & gas-cut mud, 60' heavy oil & gas-cut
mud, 330' of oil, 30' of watery mud.
IFP 0#, FFP 140#, BHP 460#/30 mins.