


FORMATION TEST REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

Company SILVER CREEK COMPLETION CORP. Lease and Well No. #1 VADEN
Sec. 12 Twp. 34S Rge. 5E Test No. 1 Date 12/22/83

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE: 12/22/83
CUSTOMER: SILVER CREEK COMPLETION
WELL: 1 TEST: 1
ELEVATION (KB): 1149 FORMATION: ARBUCKLE
SECTION: 12 TOWNSHIP: 34S
RANGE: 5E COUNTY: COWLEY STATE: KANSAS
GAUGE SN #5666 RANGE: 3950 CLOCK: 12

INTERVAL TEST FROM: 3440 FT TO: 3452 FT TOTAL DEPTH: 3452 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 3435 FT SIZE: 6 3/4 IN PACKER DEPTH: 3440 FT SIZE: 6 3/4 IN
PACKER DEPTH: FT SIZE: IN PACKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WELLWIN
MUD TYPE: CHEMICAL VISCOSITY: 40
WEIGHT: 9.5 WATER LOSS (CC): 11.2
CHLORIDES (P.P.M.): 1800
JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? NO REVERSED OUT? NO
DRILL COLLAR LENGTH: 405 FT I.D.: 2 1/4 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 3026 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 20 FT TOOL SIZE: 5 1/2 IN
ANCHOR LENGTH: 12 FT SIZE: 5 1/2 IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 XH IN

BLOW: FAIR BLOW THROUGHOUT TEST.

RECOVERED: 400 FT OF: MUDDY WATER
RECOVERED: FT OF: CHLORIDES 25000 PPM
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:

REMARKS:


TIME SET PACKER(S): 1:00 AM TIME STARTED OFF BOTTOM: 4:00 AM
WELL TEMPERATURE: 124 °F
INITIAL HYDROSTATIC PRESSURE: (A) 1752 PSI
INITIAL FLOW PERIOD MIN: 30 (B) 120 PSI TO (C) 165 PSI
INITIAL CLOSED IN PERIOD MIN: 30 (D) 1377 PSI
FINAL FLOW PERIOD MIN: 60 (E) 192 PSI TO (F) 232 PSI
FINAL CLOSED IN PERIOD MIN: 60 (G) 1378 PSI
FINAL HYDROSTATIC PRESSURE (H) 1745 PSI

3213

TKT # 3213

I

5646



3213

TKT # 3213

0

13265

