


FORMATION

TEST

REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE: 4/8/84
CUSTOMER: SILVER CREEK CORPORATION
WELL: 3 TEST: 1
ELEVATION (KB): 1184 FORMATION: KANSAS CITY
SECTION: 14 TOWNSHIP: 34S
RANGE: 5E COUNTY: COWLEY STATE: KANSAS
GAUGE SN #6074 RANGE: 5100 CLOCK: 12

TICKET #4298

LEASE: MARRS

GEOLOGIST: BAZZLE

INTERVAL TEST FROM: 2462 FT TO: 2479 FT TOTAL DEPTH: 2479 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 2457 FT SIZE: 6 5/8 IN PACKER DEPTH: 2462 FT SIZE: 6 5/8 IN
PACKER DEPTH: FT SIZE: IN PACKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WELLWIN DRLG
MUD TYPE: CHEMICAL VISCOSITY: 36
WEIGHT: 9.8 WATER LOSS (CC): 16.1
CHLORIDES (P.P.M.): 1800

JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? NO REVERSED OUT? NO

DRILL COLLAR LENGTH: 375 FT I.D.: 2.25 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 2067 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 20 FT TOOL SIZE: 5 1/2 IN
ANCHOR LENGTH: 17 FT SIZE: 5 1/2 IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 FH IN

BLOW: INITIAL FLOW PERIOD WEAK BLOW BUILDING TO A
FAIRLY STRONG BLOW.
FINAL FLOW PERIOD WEAK BLOW BUILDING
TO A GOOD BLOW.

RECOVERED: 195 FT OF: MUDDY SALT WATER. CHLORIDES 80000 PPM.
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:

REMARKS:

TIME SET PACKER(S): 6:40 PM

TIME STARTED OFF BOTTOM: 8:55 PM


WELL TEMPERATURE: 100 °F

INITIAL HYDROSTATIC PRESSURE: (A) 1285 PSI
INITIAL FLOW PERIOD MIN: 30 (B) 50 PSI TO (C) 91 PSI
INITIAL CLOSED IN PERIOD MIN: 30 (D) 920 PSI
FINAL FLOW PERIOD MIN: 45 (E) 125 PSI TO (F) 179 PSI
FINAL CLOSED IN PERIOD MIN: 33 (G) 908 PSI
FINAL HYDROSTATIC PRESSURE (H) 1271 PSI

6074
DST #1

TKT # 4298

I



TKT # 4298

6246
DST#1

