


FORMATION

TEST

REPORT



Home Office:

Wichita, Kansas 67201

P.O. Box 1599

Phone (316) 262-5861

WESTERN TESTING CO. INC.
SUBSURFACE PRESSURE SURVEY

DATE: 12/27/84
CUSTOMER: SACO OIL COMPANY
WELL: 1 TEST: 1
ELEVATION (KB): 1243 FORMATION: MISSISSIPPI
SECTION: 26 TOWNSHIP: 27S
RANGE: 10E COUNTY: GREENWOOD STATE: KANSAS
GAUGE SN #5666 RANGE: 3950 CLOCK: 12

INTERVAL TEST FROM: 2137 FT TO: 2147 FT TOTAL DEPTH: 2147 FT
DEPTH OF SELECTIVE ZONE: FT
PACKER DEPTH: 2137 FT SIZE: 6 3/4 IN PACKER DEPTH: FT SIZE: IN
PACKER DEPTH: FT SIZE: IN PACKER DEPTH: FT SIZE: IN

DRILLING CONTRACTOR: WHITE & ELLIS DRLG
MUD TYPE: CHEMICAL VISCOSITY: 40
WEIGHT: 9.6 WATER LOSS (CC): 12.0
CHLORIDES (P.P.M.): 1400
JARS - MAKE: SERIAL NUMBER:
DID WELL FLOW? NO REVERSED OUT? NO
DRILL COLLAR LENGTH: 244 FT I.D.: 2.25 IN
WEIGHT PIPE LENGTH: FT I.D.: IN
DRILL PIPE LENGTH: 1878 FT I.D.: 3.8 IN
TEST TOOL LENGTH: 15 FT TOOL SIZE: 5 1/2 OD IN
ANCHOR LENGTH: 10 FT SIZE: 5 1/2 OD IN
SURFACE CHOKE SIZE: 3/4 IN BOTTOM CHOKE SIZE: 3/4 IN
MAIN HOLE SIZE: 7 7/8 IN TOOL JOINT SIZE: 4 1/2 IF IN

BLOW: WEAK BLOW TO A FAIR BLOW THROUGHOUT TEST.

RECOVERED: 345 FT OF: MUDDY SALT WATER WITH SCUM OF OIL ON TOP.
RECOVERED: FT OF: CHLORIDES 75000 PPM.
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:
RECOVERED: FT OF:


REMARKS:

TIME SET PACKER(S): 5:15 AM TIME STARTED OFF BOTTOM: 8:15 AM
WELL TEMPERATURE: 103 °F
INITIAL HYDROSTATIC PRESSURE: (A) 1101 PSI
INITIAL FLOW PERIOD MIN: 35 (B) 20 PSI TO (C) 108 PSI
INITIAL CLOSED IN PERIOD MIN: 30 (D) 676 PSI
FINAL FLOW PERIOD MIN: 60 (E) 147 PSI TO (F) 180 PSI
FINAL CLOSED IN PERIOD MIN: 60 (G) 687 PSI
FINAL HYDROSTATIC PRESSURE (H) 1101 PSI

8029

TKT # 8029

I



TKT # 8029

O

8029

13265

