

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


31-12-15W

Company- MALLONEE DRILG. CO., INC.
Farm- Rogg No. 1

SEC. 31 T. 12 R. 15W
NE NW NE

Total Depth. 3376'
Comm. 7-8-58 Comp. 7-25-58
Shot or Treated.
Contractor. Mallonee Drilg. Co., Inc.
Issued. 11-22-58

County Russell
KANSAS



CASING:

5/8" 232' w/120 sx cem.

Elevation. 1886' KB

Production. DRY

Figures indicate Bottom of Formations.

surface clay	40
shale, sand	110
shale, shells	232
shale	460
iron	467
shale, sand	557
sand	600
shale, sand	810
shale, shells	885
red bed	945
Anhydrite	982
shale	1075
shale, shells	1605
shale, lime	1650
lime	1675
lime, shale	1995
sdv lime	2010
lime, shale	2830
lime	3024
lime, shale	3048
lime	3376
Rotary Total Depth	

TOPS:

Anhydrite (scout)	945
Topeka	2713
Heebner	2990
Toronto	3010
Lansing	3040
Gorham sand	3328
Conglomerate	3345

DST #1--3023-3055' Open 30
mins., red. 30' mud. EHP 312#

DST #2--3060-3118' Open 1 hr.,
rec. 80' gas, 60' slightly oil
cut watery mud. EHP 330#.