

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

Company - COOPERATIVE REFINING ASS'N.
 Farm - Albert Krug No. 6

SEC. 9
 NE SE NE

T. 14

R. 14W

Total Depth. 3266 D.F.

Comm. 3-30-50

Comp. 5-15-50


Shot or Treated.

Contractor. C.R.A.

Issued. 6-10-50

County. Russell

KANSAS

Elevation. 1949.9nd

Production. Pmp. 55 bbls oil /
 290 wtr in 24 hrs.

CASING:

8 5/8" 851' cem. w/450 sx.

5 1/2" 3261' cem. w/125 sx.

Figures Indicate Bottom of Formations.

shale & shells	325
sand, shale, shells	355
pyrite	359
sand	430
red bed & shale	580
red bed	847
anhyd.	875
shale & shells	1275
salt & shale	1410
shale, shells & red bed	1465
shale & red bed	1485
shale & lime	1595
lime	1610
lime & shale	1705
lime	1863
lime hrd.	1975
lime	2040
shale & lime	2740
lime	3195
shale & lime	3235
lime	3270
R.T.D. 3270 =	3266 D.F.
Total Depth	

Tops: D.F.

Tarkio limestone 2442

Elmont " " 2499

Topoka 2707

Heebner 2934

Toronto 2952

Lansing-K.C. 2992

Reagan sandstone 3260