

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CRA, INC.

SEC. 9 14 14R. 14W
LOC. C N/2 N/2 NE

FARM Albert Krug

NO. 7

TOTAL DEPTH 3275

COMM. 4-11-66


COMP. 4-21-66

SHOT OR TREATED

CONTRACTOR Rains & Williamson Oil

ISSUED 6-25-66

COUNTY Russell
KANSAS



CASING

20	10 3/4"	@ 566'	w/375 sx.
15	8		
12	6 7"	@ 3274'	w/300 sx.
13	5		

ELEVATION 1900' KB

PRODUCTION Injection Well

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS: SCOUT

FORMATIONS

Surface Soil & Clay Shale	552'
Red Bed	580'
Shale Red Bed	855'
Anhydrite	890'
Shale & Shells	1600'
Shale w/Lime	1706'
Shale & Shells	1900'
Lime & Shale	2020'
Lime w/Shale	2155'
Shale w/Lime	2660'
Lime w/Shale	2915'
Lime & Shale	2985'
Lime w/Shale	3115'
Lime	3215'
Lime & Shale	3260'
Lime	3275'
Rotary Total Depth	3275'

Anhydrite	853
*Tarkio Lime	2457
*Elmont	2515
*Burl	2183
*Howard	2659
*severy	2702
Topeka	2717
Heebner	2946
Toronto	2968
Douglas	2980
Lansing	3009
Base Kansas City	3256

* Sample Tops

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 25th day of April, 1966.

My Commission Expires: 3-3-70

Mary J. Brown
Notary Public