


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CORALENA OIL CO.
Albert No. 2.

SEC. 9 T. 14 R. 14 W
SW SE NE

Total Depth. 3042'
Comm. 8-5-43 Comp. 8-18-43
Shot or Treated.
Contractor.
Issued. 10-23-43

County. Russell



CASING:
10 $\frac{3}{4}$ " 146' 10" Cem.
7" 3024' Cem.

Elevation.

Production. Phy.Pot.470 B.

Figures Indicate Bottom of Formations.

surface clay	0-40
shale & shells	854
anhydrite	893
shale & shells	1275
salt	1500
shale & shells	1570
lime brkn	1732
lime & shale	1860
lime	2045
lime & shale	2250
shale	2470
lime & shale	2728
lime gy	2897
lime sft-saturation	2942
lime gy to wh, some shale	2976
red rock & shale blk	2983
lime wh	2999
red rock & shale	3016
lime hd	3028
lime sft, saturation	3033
lime hd	3042
Total Depth.	

Oil pay 3028-33

Tops: Topeka 2728
Dodge 2983
Kansas City 3016