


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING COMPANY
Farm- Rusch No. 1

SEC. 9 T. 14 R. 14W
NW NE SW

Total Depth. 2517
Comm. 10-29-52 Comp. 1-10-53
Shot or Treated. Dowell-Frac
Contractor. Murfin Drlg. Co.
Issued. 4-11-53

County Russell
KANSAS



CASING:

15" 383' 7" 2491'
12" 584'
10" 875'

Elevation. 1868 DE

Production. 25 BOPD

Figures indicate Bottom of Formations.

clay yellow	35
shale lgt	260
red rock	340
sand	350
shale	360
sand	383
shale	390
sand	400
shale	430
sand	450
shale	460
sand	475
shale	550
red rock	555
red shale	875
lime	915
red rock	1070
shale	1085
lime	1095
red rock	1125
shale	1290
salt	1535
shale	1545
salt	1560
lime	1575
shale, shells	1605
lime	1630
lime, shale brks	1660
shale, shells	1705
lime, shale	1730
lime	1775
red rock	1790
lime	1825
shale, shells	1845
lime, shale	1895
lime, shale	2035
lime	2050
red rock	2060
lime	2065
lime, shale	2120
shale	2135
lime	2150
lime, shale	2185
shale	2200
lime	2215
shale, lime	2240
lime	2255
shale, shells	2360
shale	2375
lime	2390
shale, lime	2400
shale, shells	2473
red rock	2475
tarkio	2508
sand brown	2517
Total Depth	

Tops:
Tarkio 2475
show oil 2490-2502'