

WELL COMPLETION REPORT
DRILLER'S LOGAPI No. 15 — 167 — 21,775
County Number

Operator

Oil Producers of Ellis Co.

Address

27 Canterbury Hays, Kansas 67601

Well No.

#1

Lease Name

Ralph Dumler

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Revlin Drlg., Inc.

Geologist

Nicholson

Spud Date

8-29-81

Date Completed

9-5-81

Total Depth

3350'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20#	223'	Sun set	160	
Production	7 7/8	4 1/2	9.5#	3349'	60-40 Poz Mix	175	5% Gilsonite 2% Gel 10% Salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
		3278-84

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
6-7/84 SQZ 373-418 WITH 125 SX. RUN MIT AFTER CLEAN OUT TO PLUG AT 2900, HELD OK. PERK 3092-96 3141-46, 3195-96, 3212-13, 3233-37 & 3272-82. For Injection	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	McF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.


NO CARD

S. 6 T. 14 R. 14 E

Loc. SE SW NE

County Russell

640 Acres



Elev.: Gr.

KB 1876' KB

AUG 15 1985
State Geological Survey
WICHITA BRANCH

Operator Oil Products of Ellis Co.		DESIGNATE TYPE OF COMPLETION: OIL, GAS, DRY HOLE, SWD, ETC.:	
Well No. #1	Lease Name Ralph Dumler	Oil	
S <u>6</u> T <u>14</u> R <u>14</u> E W SE SW NE			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Shale & Postrock	0	40	R.T.D.
Shale-Shells-Sand	40	226	
Clay - Sane	226	344	
Shale	344	897	
Anhydrite	897	935	
Shale	935	1630	
Shale w/ Lime	1630	3270	
Lime-Sand Dolomite	3270	3315	
Arbuckle	3315	3350	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<i>Paula J. Gibson</i> Signature Bookkeeper Revlin Drlg., Inc. Title September 8, 1981 Date		