


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
 Farm- S. Boxberger No. 8

SEC. 10 T. 14 R14W
 NE NW NW

Total Depth. 3243
 Comm. 10-23-53 Comp. 11-17-53
 Shot or Treated.
 Contractor.
 Issued. 1-9-54

County Russell
 KANSAS



CASING:
 10 3/4" 830' cem. w/600 sx
 7" 3243' cem. w/225 sx

Elevation. 1833' RDB

Production. Pmp. 81 B0

Figures indicate bottom of formation.

shale & shells	250
shale, lime & pyrite	560
shale, shells,	
anhydrite	832
anhydrite	855
shale & shells	1505
shale & lime	1860
lime	1905
lime & shale	2368
shale & sand	2428
lime & shale	2850
lime	3176
lime & shale	3238
Core #1	3243
Total Depth	

TOPS:
 Tarkio 2368
 Lansing 2979
 Reagan 3242

CORE #1 3238-43'
 Rec. 4'. Top 2 1/2' dense
 green shale, w/pyrite
 inclusions. 1 1/2" dolomite
 w/shale & large chert
 inclusions. Sand in bottom
 6". Bleeding oil in spots.
 sulphureodor in bottom of
 core.

D.S.T. #1 2981-3004' Tool
 open 1 hr. Rec. 65'
 hvy oil cut mud &
 salt wtr, BHP 310#.

D.S.T. #2 3060-71' Tool
 open 30 min., rec.
 5' mud, BHP 15#.

Well Completed Natural.