

10-62

STATE KANSAS	COMPANY EMPIRE
COUNTY RAWLINS	FARM BEESON
BLOCK	WELL NO. 1
SEC. 18	SURVEY
T. 3	R. 35W
TOTAL DEPTH 4890'	
C SW SW	
COMMENCED	
COMPLETED	
REMARKS E Log	
ALTITUDE	
PRODUCTION 249 BOPD	

CASING RECORD

DST #1 (Lens) 4199-4220: Op 60";
R 30' MUD, IBHP 78[#], FP'S 15-31[#]
FBHP 36[#]/NT.

DST #2 (Lens) 4225-55: Op 60", R
60' HOCM, IBHP 1436[#]/NT,

SHOT QUARTS BETWEEN
FP'S 7-36, FBHP 1062[#]/NT

Krafft 186 ROSS-MARTIN CO. TULSA 1, OKLAHOMA PRINTED IN U.S.A.

DST #3 (Lens) 4248-82:
Op 60", R 28' SOC M,
IBHP 534[#]/NT, FP'S
14-28[#], FBHP 51[#]/NT

DST #4 (Lens) 4377-4405:
Op 1 hr, 160' GIP, R 190'
H O & GCM = (est.) 60%
OIL, IBHP 1284[#]/30",
FP'S 31-86[#], FBHP
1173[#]/30".

DST #5 (Lens) 4405-40:
Op 1 hr, R 120' VHO &
GCM + 105' clean oil,
Gr 36° @ 80° + 15' Wtr,
IBHP 1286[#]/30", FP'S
31-114[#], FBHP 1157-30"

DST #6 (Chera) 4638-71:
Op 1/2 hr, R 10' MUD w/SLI
SCM OIL, IBHP 1157[#]/30
IFP 12[#], FFP 23[#]
FBHP 133[#]/30".