

STATE Kansas		COMPANY Hendon Drlg.	
COUNTY Decatur	FARM Bader #1		WELL NO.
BLOCK	SURVEY		
SEC. 20			
T. 5	R. 26W	TOTAL DEPTH	
		COMMENCED	
		COMPLETED	
ALTITUDE		REMARKS NW-NW-SW	
PRODUCTION			

CASING RECORD		
SHOT	QUARTS	BETWEEN

FORM 186 - In stock and for sale by Ross-Martin Co., Tulsa

100

200

300

400

500

600

700

800

900

1000

1100

1200

1300

1400

1500

1600

1700

1800

1900

2000

2100

2200

2300

2400

2500

2600

2700

2800

2900

3000

3100

3200

3300

3400

3500

3600

3700

3800

3900

4000

4100

4200

4300

4400

4500

4600

4700

4800

4900

5000

dominantly g. sh. with brn. sideritic sand.

g. wh. f. g. sub-vit. sst.

g. sh. included. g. f. med.

g. pyritic sst. & sideritic sand pebbles

g. wh. f. med. g. sub-vit. sst.

15 Morrison 1615

green-g-b. & purple sub-plastic sh.

g. chalky sandy ls. interbedded. li. green sub-plastic sh.

green & brn. sub-plastic sh. & g-bf. chalky ls. streaks.

green-g. & brn. sh. streaks. wh-g. anhy.

Permian Redbeds 1825

25

Reddish-brn. sh. sandy in part.

Here (caving badly)

sand. streaks. wh-g. anhy. in R-brn. sandy sh.

40 Cimarron Anhy 2240

g. wh. massive anhy

Reddish-brn. sh. streaks. wh-g. anhy. included. pale green sh. streaks.

Reddish-brn. sandy anhy. sh.

Reddish-brn. gray & green. anhy. sh.

Fe. Riley? 2750

50

cr-g-bf. sand. dense dolo. g-bf. con. f. xln. to suc. sh. por. cr-g. d. sand.

g-bf. d. sand.

cr-g. wh. f. med. xln.

cr-g. sand. f. xln.

R-g. sh. streaks. g-bf. f. xln. dolo.

g. wh. f. chalky fos. ls.

g-bf. f. fos. dolo. in part.

cr-g. f. fos.

g-cr. f. fos. shaly at top.

g. d. f. dy.

g-bf. f. dolo. broken with R-g. sh.

g-bf. f. dolo. ls.

g-cr-bf. f. dy. ls.

g-bf. f. dy.

cr-g. f. dy.

g-cr. f.

g-bf. d. f.

g-cr. f. fos. ls. streaks. interbedded. R-g. sh.

g-cr. f. med. xln.

cr-g. f. **Forney**

22 Topoka 3422

g. d. f.

g-cr-bf. d. to f. fos.

cr-wh-g. f. fos. sh. por. in part.

g. wh. d. f.

wh-cr. f. fos. por.

cr-g. wh. f. por. fos.

cr-g. f. xln. dolo. ls.

Heebner 3695

cr-g. wh. f. fos. por.

g. d. f. dolo.

95

cr. d. f.

wh. d. f. dy **Lansing 3722**

22

cr-g. wh. d. f. dy. streak dolo. por. sp. det. oil st.

wh-cr. d. f. sp. det. oil st.

wh. dense dy. sh. dolo. por. Tr. bf. d. f.

wh. d. f. dy.

Samples Worthless

wh-cr. d. f.

wh-cr. d. f.

wh. d. f. dy

dominantly R-brn. sh. with streaks cr. g. d. f. xln. ls.

P.B.C. 4083

Vg. sh. sandy sh.

abundant. Wh-v. cl. A. in Vg. sh.

deeply oxidized. sm. type sandy sh. & wh. med. xln. siliceous dolo. pebbles wh. Vg. sh. & v. cl.

62

g. wh-bf. co. xln. vug. por.

Arbuckle 4162

bf. co. xln. iron st. por.

bf. co. xln. sh. sandy & glauconitic. (even stained)

55

T.D. 4235