

Log of Well drilled by Hazlett, Decker & Wells on the Ware Farm located in the SE corner of the SW $\frac{1}{4}$ of Sec. 18--22--18, Anderson County, Kansas. Spudded August 9, 1926. Completed August 27, 1926. W. H. HAZLETT, CONTRACTOR.

Soil	TO	5
Clay yellow		25
Shale Blue		120
Lime White		155
Shale Black		165
Lime White		230
Shale White		335
Lime Iola		385
Shale White		405
Lime		410
Shale Red		420
Shale Blue		450
Lime White		500
Shale Black (Wtr. 5 B)		505
Lime White		530
Shale Dark (Wtr)		535
Lime Sharp		566
Slate		567
Slate White		587
Sand		600
Slate Blue		725
Lime Shelly		735
Shale White		740
Lime Solid		753
Shale White		775
Sand White (Wtr. $\frac{1}{2}$ B.)		800
Shale Light		815
Lime		825
Shale Black		840
Lime		845
Shale Black		860
Shale White		880
Lime Sharp		890
Slate Black		900
Lime		905
Slate light & Black		960
Lime		965
Slate Blue		995
Lime		1000
Sand Blue		1040
Sand (Little Wtr)		1050
Shale Black & Blue		1130
Sand Slate		1145
Sand		1147
Sand (Wtr. Hole filled up)		1277
Shale Black		1282
Shale White		1300
Mississippi Lime		1305
Lime Light		1325
Shale Black		1330
Shale & Lime		1365
Lime White		1367

Casing Record.	
12 $\frac{1}{2}$ "	20
10 "	567
8 "	1155
6 $\frac{1}{2}$ "	1505

STATE OF KANSAS, MONTGOMERY COUNTY, SS.

I, the undersigned, being duly sworn on oath states that the above and within statement is true and correct record and log of the well drilled at the location above described.

W. H. Hazlett

Subscribed and sworn to before me this 28th day of August, 1926.

Wilma Wycoff
Notary Public

My Commission expires November 13, 1929.

