

6-54

STATE	Kansas	COMPANY	J.-S.-F.		
COUNTY	Norton	FARM	Wilds	WELL NO.	1
BLOCK		SURVEY			
SEC.	16				
T.	4	R.	22W	TOTAL DEPTH	3892'
					Sw-Sw-Nw
				COMMENCED	
				COMPLETED	
				REMARKS	
ALTITUDE	2365				
PRODUCTION	D&A.				

CASING RECORD		
DST 3584-361V/hy		
290' g/t. wtr. BHP 1240.		
SHOT	QUARTS	BETWEEN

FORM 186 - In stock and for sale by Ross-Martin Co., Tulsa

100	R. B. S.
200	
300	
400	
500	
600	
700	
800	
900	
1000	
1100	
1200	
1300	
1400	
1500	
1600	
1700	
1800	
1900	
2000	
2100	
2200	
2300	
2400	
2500	
2600	
2700	
2800	
2900	
3000	
3100	Samples Start @ 3200'
3200	gry bf f foss crm gry fd crm gry f foss crm gry f gran dolo. ls. crm gry f foss gry ltb f fd crm gry bt f d clay crm lt gry f foss streaks ppor.
3300	crm lt gry f foss ay. crm gry fd foss crm fd crm lt gry f foss streaks ppor. crm lt gry fd crm lt gry fd foss b/k sh gry btd wh crm f foss qool. ay scat oblie por crm lt gry fd crm lt gry fd ay in part scatoolic por. faint stn.
3400	crm gry fd crm f foss scatoolic por. 3 clay crm gry fd clay crm gry fd foss gry fd ool scatoolic por. spots 4 stn crm gry fd crm fd scaly ls 30 vq sh q. tr. vcol d w/ mgd to cgr L to 43 crm gry subvnd quartzitic, sst 54 wh f to cgr poorly sorted sl. glauconitic 66 subvnd frosted sst. avkasic in part 80 weathered pink feldspar & quartz fresh pink feldspar, biotite mica & quartz
3500	P.B.C. 3830 (BANNETER) RB 3843 "PALEOZ. BASAL Sst 3880" "GRANITE WASH" 3880' PRE CAMB GRAN. 3885
3600	T.D. 3892' sple TD 3890'