12-55

STATE	Kansas
COUNTY	Phillips
BLOCK	
SEC.	19
T.	4
R.	20W
ALTITUDE	2101
PRODUCTION	D&A
COMPANY	Anschutz
FARM	Noel
WELL NO.	1
SURVEY	
TOTAL DEPTH	3687
LOCATION	Sw-Nw-Nw
COMMENCED	
COMPLETED	
REMARKS	

CASING RECORD

SHOT	QUARTS	BETWEEN

FORM 186 - In stock and for sale by Ross-Martin Co., Tulsa

100
200
300
400
500
600
700
800
900
1000
1100
1200
1300
1400
1500
1600
1700
1800
1900
2000
2100
2200
2300
2400
2500
2600
2700
2800
2900
3000

Samples Start 3060



g, dse
g-bf, d-f, fos mottled lst
TP 3102
~~rx g, sli sdy sh, orn g, f.g.~~
~~sdy, f.g., ooc, sst.~~
02 g-bf, d-f.
lt. g, soft por. fos Δy lst
g, soft friable calc siltstone
wh, d-f, fos Δy
c, dse Δy
3200
rx g sdy sh.
c, d-f, fos
"wh, d-f, fos. Δy lst.
wh to c, d-f, sli Δy lst.
99 blk sh. Hbnr Sh 3299
3300
96 g.bf, dse lst
rx g sh.
24 wh, f, fos. Δy
Ls 3342
rx g sh.
42 wh, por. ooc. Δy lst.
c, dse Δy
wh. to c, d-f.
Δy, por. & ooc. at base. sli dolomitic in part
c, d-f, profusely Δy lst. f. oil stn
3400
wh, d-f, Δy, scat ooc. por & trace oil stn
wh, d-f, Δy
wh. to c, d-f.
wh, dse, Δy
wh, to c, d-f, Δy
c, d-f, scat ooc. por & sli spotty dk oil stn.
3500
c, g. d-f
wh, dse
wh, d-f, co. ool. lst.
g, dk g sh.
bf fri... stained ool lst
g.f.g. soft friable calc. sst
rx g sh.
wh, d-f.
3600
"wh, f.g., glassy subc sst
wh, dse
PBC 3635
" 35
rg, sdy sh & v. col. Δ
56
lt. g to bf, med to co. xln. dolo
80 skip
87 TD
Arb 3656
3700
20 Total depth 3687'
~~Samples 3720 to 3775 but are worthless & possibly mixed up with some other well~~
3800
~~Total Depth (sample) 3775~~
3900