

STATE Kansas		COMPANY Wood River	
COUNTY Graham	FARM Faulkner 'A'		WELL NO. 1
BLOCK	SURVEY		
SEC. 27			
T. 10S.	R. 22W.	TOTAL DEPTH 4100	
		SW-SE-SE	
		COMMENCED	
		COMPLETED	
		REMARKS	
ALTITUDE 2313			
PRODUCTION 406 BOPD Lans			
CASING RECORD			
Perk 3956-63, 540, 250 Acid, 2800'			
A w i h + u s s o s q u e e z e P e r k 3967			
72, 1 G O P H + t r u t r, 500 Acid,			
S w b 380 B W + 15 B O P D ; P B 3912			
P e r k 3884 92, B a i l 7 B O P D, n o u t r			
SHOT 250 Acid, 1 swb 10 BOPD, 1200' Acid		QUARTS BETWEEN	
Hra/fblt 186-B ROSS-MARTIN CO. TULSA 1, OKLAHOMA PRINTED IN U.S.A.			
Swb 25 BOPD + tr u t r			
P B 3800			
P e r k 3629-33, 1000' o i l / s h			
P u m p 4 B O P H 500 Acid			
P u m p 19.18 B O P H / 16 h r			
f. 406 B O P D n o u t r.			
Kenny Smith			
Samples Start @ 3500'			
3500	00 gray-fxl chky, poorly chalcyl lst		
	10 red + gray sh		
	17 gray-fxl sh, sl chky lst		
	25 blk carb sh		
	32 gray-crm, fcln, ls lst		Heebner 3530
	33 red + gray sh		
	64 crm-dse-fxl sh, sl chky lst		Lansing 3569
	69 red + gray sh		
	79 gray-crm, fcln, sl chky lst w/ good por & fair- good lt. str.		
3600	00 gray-crm-dse, sl chky lst		
	09 red + gray sh		
	20 crm-fxl lst w/ dr. of por & v. lt. spotted str		
	red + gray sh & gray-fxl, chky lst w/ good		
	44 por & good sat; por is pp		
	red + gray sh & gray-dse-fxl lst w/ streak of		
	69 good por in pt. w/ good sat; por is pp		
	lt gray-crm, dse lst		
	92 red + gray sh & gray-dse lst		
3700	08 gray-crm-dse-fxl lst w/ streak of fair por		
	24 & lt spotted str		
	red + gray sh & crm-buff, dse lst		
	lt gray-crm, dse-fxl, lst w/ streak of fair		
	65 vol por & good str to sat at base		
	red + gray sh & lt gray-crm-dse lst		
	94 gray-crm-buff, fcln lst		
3800	02 red-gray & greenish-gray sh		
	24 gray-crm-dse-fxl lst		
	sh as above w/ streak of gray-crm-buff		
	fcln lst pink lst		
	58 mostly red sh		Marmaton 3877
3900	77 gray & orange chky in gray-fxl ls, ls		
	lst; 50% of chky is trip w/ a poor		
	04 por & scat dead str.		
	red + gray sh		Congl sd 3957
	32 var. chky & dr. on a dr. sub ang		Arbuckle 3965
	65 sat w/ spotted str to sat		
	gray-whitish-med-xln dolo w/ spotted		
	poor-fair por & spotted heavy oil ch		
	good sat where poor		
4000	15 heavy blk oil residue		
	gray-crm-buff-med-crm-ls chky dolo		
	30 w/ streaks of white por.		
	crm-buff, med-crm-ls, sctly suc, sctly		
	sandy ls chky dolo		
	86 gray-crm-ls, muggy dolo; good por		
4100			
total depth 4100'			