

Kans.
Ottawa

WICHITA LABORATORY

SEP 18 1944

Phillips

COMPANY

Kather

NO. 1

COMMENCED 8/1/44

COMPLETED 8/30/44

REMARKS SW SW SW

T.D. 3630 Pot

D+A Lag by J.C. Condon

T. 115 R. 1W

15

15

ELEVATION

1380

PRODUCTION

FORM 187 - In stock and for sale by Mid-West Prtg. Co., Tulsa

100

200

300

400

500

600

700

800

900

1000

1100

1200

1300

1400

1500

1600

1700

1800

1900

2000

2100

2200

2300

2400

2500

2600

2700

2800

2900

3000

3100

3200

3300

3400

3500

3600

3700

3800

Sample start at 1800

dolo: crm. suc.

LK 2055

ls: wht. to crm. chalky to micro-xlm.

w/ scath. ool.

ptly. fm. ool.

crs. meta-ool. good por.

dns.

w/ small lime nod.

w/ vari-color sh.

vari-color sh.

So 2680 not corr. for lag

ML 2688

ls: orange, jagged ool. & crs. dolo: buff & gray-buff suc. & fm. suc.

ls: wht. mott. gray vit. to devit. app. w/ 9/2 goodes

ls: buff crs. xlm. glauc. ool: wht. to crm-buff vit. to dull

dolo: dk. brn. suc. dolom. ls: gray-brn. gran. & fm. xlm. dolo: buff suc. w/ wht. mott. buff & blue-wh. vit. to dull app. dolo. is ptly. silty.

ls: w/ scath. dolo. xlm. ls: crs. xlm. crinoidal

ls: buff & gray-buff crs. ool. also ls: buff crs. xlm. ls: ool.

w/ fine hematite oolites

Kh 2897 not corr. for lag

H 3083

dolo: dull buff med. to crs. xlm. vugular

lt. gray in pt.

lt. gray less rugs

IS 3285

w/ wht. vit. app. to sub-transl. o dolo: buff to lt. gray suc. to fm. xlm. w/ scath. fm. rugs

sh: green-gray & gray dolom. ptly. w/ div. fm. blk. specks

V 3387

interxlm. w/ dolo: buff fm. to crs. xlm. w/ good ls: wht. crs. xlm. ptly. gray spotted w/ 9/2 goodes fm. ool. dolo: brn. suc. to gran.

Sn 3485

ls: buff crs. xlm. dolom. dolo: brn. crs. to fm. xlm. good por.

ss: dolom. w/ fm. to med. rad. & sub-transl. polished & frosted grs.

dolo: gray-buff fm. suc.

fish scales

dolo: buff fm. to med. xlm. granular. w/ 9/2 goodes w/ some wht. & wht. & buff mott. w/ 9/2 goodes

ss: to fm. to sub-transl. infor. ptly. dark xlm. cherty devit. chert

entirely to crs. xlm. neg. por. w/ wht. vit. app. to sub-transl. wht.

T.D. 3630

D+A.

2-V-26

Sil 3083

Mg. dol 3265