2-58

STATE: Kansas	COMPANY: Tenn Gas & Tran
COUNTY: Rooks	FARM: Swald · WELL NO.: 1
BLOCK	SURVEY
SEC.: 6	
T.: 9 · R.: 19W	TOTAL DEPTH: 3730
	NW-NW-SE
	COMMENCED
	COMPLETED
ALTITUDE: 2096	REMARKS: electrolog
PRODUCTION: D&A	

CASING RECORD

DST 3375-82 / 1 HR, 15' MD & WTR
BHP 785 #
DST 3493-3512 / 1 HR, 11' M SS FK
0 BHP 48 #

SHOT	QUARTS	BETWEEN

FORM 186 - In stock and for sale by Ross-Martin Co., Tulsa

100 200 300 400 500 600 700 800 900 1000 1100 1200 1300 1400 1500 1600 1700 1800 1900 2000 2100 2200 2300 2400 2500 2600 2700 2800 2900 3000 3100 3200 3300 3400 3500 3600 3700 3800 3900

Samples Start @ 3000



86 TOP
95 HB
18 TOR
36 LS
91 CONG
99 ARB

lt g, soft p.p. fos, sli dolo lst
r&g sdy sh.
c-g, f, d, f, fos, shaly in streaks
r&g sdy limey sh
TP 3084
- 84 g-bf, d-f, fos. fusulinids abundant in part
c-g, soft por, fos. sli ay lst
dk g sh
g-bf mottled, f fos. ay
c-g, d-f, gran, fos. ay sli dolo/lst
dk g to blk sh.
c-g, d-f
g, d-f, fos. ay, sli dolomitic in streaks
lt g, f fos ay
wh to g, d-f, fos. ay for most part. streaks p.p. por.
Heeb Sh 3294
- 95 blk sh
- 97 g-bf, d-f
- 04 r&g sh
- 16 wh, d-f, fos, sli ay, sli dolo lst
- 30 r&g sh
- 34 wh to g, d-f, ay, p.p. por, at top
LS 3336
red, g, & dk g sh
c-g, d-f, fos. sli ay, scat ooc por, & sli spotty oil stn
c, d-f, sli ooc, por at top
c, d-f, gran. por. ay dolo lst
c, d-f, ay
r&g sh
g-bf, d-f, fos.
c, d-f, fos. scat ooc por
dk g sh
g-bf
c, d-f, scat ooc por & sli spotty oil stn
ay at top.
blk sh
c-g, d-f
PBC 3590
r&g limey sh
c, d-f, fos. ay, faintly ool, lst
r&g sh
c, d-f, fos. sli p.p. por. & trial sh
dominately varicolored & with traces of sdy vg. sh.
vg. sh. with tr. sd & ▵
33 almost 100% buff-white, chalky, op. tripolitic ▵
56 dominantly wh. ▵ as above but with some vg sh & v (ol.) ▵
waxy, highly varicolored sh at base
- 83
Arb 3693
wh to bf, med. xln. to rhombic, vuggy, por. tripolitic dolo
Samples to 3725
TOTAL DEPTH 3730