

DX 78-1 Gove

KANSAS

Section 25 Township 13 Range 30W

Well No. #1 Moore

Company O. A. Sutton

NORTH

0								4

SOUTH

WEST EAST

KANSAS

SEC.	TWP.	R.
25	13	30W

WELL NO.

#1 Moore

FARM

COMPANY

O. A. Sutton

CONTRACTOR

Lewis Drlg.

Wildcat.

330

Ft. from N. Line

Ft. from S. Line

Ft. from E. Line

330

Ft. from W. Line

NW NW NW

A 10x10 grid map. The top edge is labeled 'NORTH', the bottom edge 'SOUTH', the left edge 'WEST', and the right edge 'EAST'. A blue '0' is located in the top-left cell (row 1, column 1).

1954	ELEVATION 2874'	REPORT
11/11	M I R	
12/22	Spud 11-11-54 Oil Well TD 4720' 8" @ 190' Heeb 3877' Top 3631' Tor 3899' Lans 3916' DST 3919'-31' opn 1 hr, rec 70' Mud 1025# DST 4005'-25' opn 1/2 hr, rec 210' s.w. 1170# DST 4119'-33' opn 1 hr, rec 3020' gas, 50' hocm, 450' clean oil 1160# Miss 4492' DST 4493'-4500' opn 1 hr, rec 5' Mud. DST 4505'-18' no rec. Viola 4644' Arb. 4685' TD 4720' 5" @ 4214' CO to 4200' 48/ 4122-30 S/ 4 1/2 boph 2000 A S/ 22 boph 6 hr. S/ 19 boph 8 hr. P/ 110 bopd. Comp 153 bopd.	
		COMPLETED

DX-78

County Gove State KansasSec. 25 (Blk. 13) (Sur. 30W) Map No.Operator O. A. SuttonWell No. 1 Farm MooreElev. Location NW NW NW

0									

330 Ft. From N Line NW330 Ft. From W Line QuarterIst. Report NOV 10 1954

Completion

Remarks


Lewis Drlg. - Contr.

Spudding Date

Drlg. Data WildcatM I R

FABEN GILSTRAP

County Gove State Kansas
 Sec. 25 (Blk.) 13 (Sur.) 30W Map No.
 Operator O. A. Sutton
 Well No. 1 Farm Moore
 Elev. 2874 Location NW NW NW



330 Ft. From N Line NW
330 Ft. From W Line Quarter

1st. Report

Completion DEC 22 1954

Remarks Wildcat

Lewis Drlg. - Contr.

Spudding Date 11-11-54

Drlg. Data Oil well TD 4720

8" @ 190 Heeb. 3877 Top. 3631

Tor. 3899 Lans. 3916 DST 3919-31

open 1 hr. Rec. 70' mud 1025#

DST 4005-25 open 1/2 hr. Rec. 210' sw

1170# DST 4119-33 open 1 hr. Rec.

3020' gas 50' hocm 450' clean oil

1160# Miss. 4492 DST 4493-4500

open 1 hr. Rec. 5' mud DST 4505-18

no rec. Viola 4644 Arb. 4685

TD 4720 5" @ 4214 CO to 4200

48/ 4122-30 S/ 4 1/2 boph 2000 A

S/ 22 boph 6 hr. S/ 19 boph 8 hr.

P/ 110 bopd Comp. 153 bopd

FABEN GILSTRAP