

STATE Kansas		COMPANY Bay Petro.	
COUNTY Salina	FARM Royce		WELL NO. 1
BLOCK	SURVEY		
SEC. 13			
T. 15 S	R. 4 W	TOTAL DEPTH 3437	
		SE-SE-SE	
		COMMENCED	
		COMPLETED	
ALTITUDE 1292		REMARKS	
PRODUCTION D.E.A.			

CASING RECORD

DST 3431-34/1hr, rec 175' muddy
w/sum of oil BHP 1200#/15"

SHOT	QUARTS	BETWEEN
------	--------	---------

186-B

ROSS-MARTIN CO.
TULSA 1, OKLAHOMA

PRINTED IN U.S.A.

Kenny Smith

2800

varic sh; silty in pt; streaks buff-brn; xly argill. lst

Mississippian 2873

72 73 lt gray-white sf. xln, suc. dolo w/ fair suc por

74 streaks med-co xln lst

75 lt gray-med xln, sl glauc. lst; sl dolom in streaks

76 dk gray-buff, f. xln, suc dolo w/ good ung

77 gray-crm, med-mco xln, sl glauc. lst

78 gray-buff f. xln, suc dolo w/ good suc & ung por & co. xln, dolom lst

79 buff-brn, suc, u. por dolo

80 gray f. xln, suc, sl chty, glauc dolo; fair por

81 gray-buff f. co xln, glauc, chty lst; dolom

82 lt gray - gray med-co xln, chty lst

83 lt gray-white, opaque, fresh & partly trip cht.

84 crm-buff f. xln, limy, u. chty dolo

85 gray-crm buff, med xln, sl chty lst; ool in pt.

Kinderhook 3186

86 gray - dk gray, brn & med sh; yellow in pt.

Misener 3315

Hinton 3326

15 15 clear f. - co. qtz, sub ang; poorly sorted; fri. to

20 20 quartzitic est.; good por where fri; us

25 25 dk gray-bn, med xln, u. sand, shaley dolo; good por

30 30 buff-brn med xln, chty, u. por, ung dolo

35 35 white - lt gray med xln, chty, u. por, ung dolo

40 40 gray-buff f. xln, suc, sl chty dolo; poor fair us

45 45 gray f. xln, suc, sl chty dolo; poor fair us

50 50 gray-grn, glauc, yellow & red ch

Maquoketa sh 3356

30 30 buff-brn med xln, sl chty dolo; good ung por & good even sat; chit is dk gray, opaque & speckled

Maquoketa Dolo 3431

Total depth 3437'