

STATE KANSAS	COMPANY AMERICAN DRILL
COUNTY RUSSELL	FARM STOPPEL
BLOCK SE-NE-SE	WELL NO. 5
SEC. 24	SURVEY
T 14	R. 11
TOTAL DEPTH 2873	
CONTRACTOR H-30 INC. Rig 11	
COMMENCED 3-29-72	
COMPLETED 4-4-72	
REMARKS ANHY 456.482 (+1218)	
GEOLOGIST Richard M. Foley	

CASING RECORD
 8 5/8" 29" USED @ 250 / 1655 AX
 5 1/2" @ 2871 / 755 AX
 Shoe: 11'

SHOT QUARTS BETWEEN

TIME RATE SCALE: 1/10" = MINUTES

450 HESS, MARTIN CO. TULSA, OKLAHOMA PRINTED IN U.S.A.

TIME RATE: 1/10" = QUARTS

2000

DST #1; 2055-2075

OPEN: 2 1/2 hr (30-60-120-60)

Weak blow

RECOVER: 120' GAS

20' mud, Heavy blk oil

Show in Top of Tool

Low gravity

60" SIP: G3 - G3

FP: 18" - 18" Hyd 1131

GRANDHAVEN 2054 (-389)

Headgrains porous sand

few clusters good sand

show gas in fine oil globules

DOVER

DST #2; 2078-2135

Open 30 min; weak blow

RECOVER: 20' mud wait

spks.

30" FSIP: 126" FP 55"

Fine grained sand, blk carb-

streaked. Thin lamination of

light dark gray blk shale.

Five grained porous sand

in streaked. Fine bluish and

abundant gas bubbles.

TARKIO LM

2135

(-461)

ELMONT 2202 (-528)

HOWARD 2340 (-666)

Thin fossiliferous

light gray fine sand

sl. stain.

2380

TOPEKA (-706)

DST #3; 2405-2430

Open: 3hr: 30-60-150-60

Good blow: Bob 8 min.

RECOVER: 600' GAS

20' SL. OG mud.

60" SIP: 142 - 94

FP: 23-39

2417 (-743)

WILSON CRK TOPEKA

Thin gray fossiliferous

fine earthy dolomite

fossiliferous, w. lt stain. sl

2500

light gray fine sand

ext. dolomite.

light gray cherty limestone

2580

2600

2620

2640

2660

2680

2700

2720

2740

2760

2780

2800

2820

2840

2860

2880

2900

2920

2940

2960

2980

3000

3020

3040

3060

3080

3100

3120

3140

3160

3180

3200