

WELL RECORD

24-28-19E

Well No. 1 Farm Bartholomew Producer Keas Drilling Co.

Location S 7/8 of Sw 1/4 Less RR right of way Sec. 24 Twp. 28 Rg 19

Elevation State Kansas County Neosho

Kind (Oil, Gas, Water, Dry Hole) Contractor

Producing formation Top Bottom

Shot with qts. from to

Packer Set at 553' Kind Size

Liner from to Perforated from to

LOG

Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
5	Soil	5	5	Blackshale	587
27	Sand, clay	32			
2	Gravel	34			
20	Lime	54			
6	S shale	60			
15	Limeshells	75			
6	Shale	81			
8	Lime	89			
35	Shale	124			
34	Lime	158			
12	Lime	170			
65	Shale	235			
45	Lime	280			
4	Lime	284			
43	Shale	327			
13	Lime	340			
10	Lime	350			
8	Shale	358			
4	Lime	362			
5	Shale	367			
17	Sand	384			
7	Shale, sandy	391			
9	Shale	400			
32	Shale	432			
38	Shale	470			
3	Lime	473			
53	Shale	526			
22	Shale	548			
3	Oil sand	551		(poor wash)	
5	Oil sand	556			
6	Oil sand	562			
4	Oil sand	566		(fair wash)	
5 1/2	Coal, sand				
	and shale	571 1/2			
5 1/2	Sandy shale	577			
5	Sand, dry	582			

Total Depth 587'

Open Hole

Casing at

Casing at

Casing at

Cement

Tubing

Rods

Additional Information

34' drive pipe

Run steel line 526'

Plugged back to 564' with
4 1/2 sacks of cement

Run 552' tubing packer

Seat nipple & collar 552'

2 gal. Konset

20 sacks of cement on top of
packerBottom of hole after plugged
back - 564'

Pulled pipe

Little gas 350 - 358'

KEAS DONATION

SEPTEMBER 1991

Date Completed Dec. 31, 1952 O. K.

Superintendent