

Range **11** Township **24 S** Section **13**
STAFFORD, County
O.J. HARTNETT, No. **9,** Farm
STANOLIND OIL & GAS CO., Company
 Sec.

0		

 Twp.

6	5	4	3	2	1
7	8	9	10	11	12
13	14	15	16	17	18
19	20	21	22	23	24
25	26	27	28	29	30
31	32	33	34	35	36

CWL NW 3818
 Elev. _____ T.D. **3781'**
 Date Drilled **2-25-39.**
 Correlation by _____
PROD. POT. 581 Bbls
NO WTR.



✓ 4 CLAY

X

X

X

X

X

Core Record
 Core #1. 3758-70' 6' Rec.
 shale green 3758-60'
 limestone grey sdy w/s.o. 3760-62'
 sand hrd tight fine grained
 with fair sat. 3262-70'
 Core #2. 3770-75' 3' Rec.
 sand sft sat. 3770-71'
 sand very shaly hrd, no sh. 3771-72'
 sand hrd tight, s.s.o. 3772-74'
 sand hrd coarse, G.S.O. 3774-75'
 Core #3. 3775-81' 5' Rec.
 sand med hrd, coarse, fair
 show oil. 3775-79'
 sand coarse blk, s.s.o. 3779-80'
 Dol. grey, no sh. 3780-81'.
 ✓ MISENER.
 DOL. VIOLA.
 T.D. 3781'.
 dolomitic
 dolo.
 T.D. 3818.

Deepening Record-
 8-30-40
 Pot. 17,780 Bbls wtr.