

A-4-222 12-84
MAP NO. 2722GR, 2730EDF
STATE Kansas COUNTY Seward
SEC. 25 Twp 33S Rge 31W
ELEV. 2722GR, 2730EDF

OPERATOR Shamrock Oil & Gas Corp. - Amarillo, Tex. loc. C SW SW
WELL NO. 3 FARM NAME Simonson
Kistmet (PD 6000)
FR. 2-9-61 SPUD 2-27-61
COMP. 4-23-61

CONT./GEOL. D&M Drilling Co.
NAME PRODUCING INTERVAL
FROM - TO 4882-88
PERF. W/HOLES 12
TREATMENT RECORD 1000 AC
ST. Louis 5776-5836
92
12,000 AC
D I. P. OIL/DIST. 24 HRS. 24
CHK. P 1/4" 24
F/225 BOPD (Calc fr 8 hr tst) " " " " " "

SIP# 200(a):940(b) FI CP# 85 (a) SIBHP 5915
COR. GR. 32°(a):38°(b) PD
CASING - CEMENT RECORD
DEPTH W/SAK. TD W/SAK.

SIZE 9 5/8" DEPTH 1531
200 750
7" 5910

OPERATOR Shamrock Oil & Gas WELL NO. #3 Simonson
ELEV. 2730: EDF

SAMPLE TOPS DEPTH SUB SEA ELEC. TOPS DEPTH SUB SEA

Toronto 4286 Council Grove 3070
Toronto Lansing Maraton
Morrow Ste. Genevieve St. Louis
5740

Spud 2-27-61, 9 5/8" @ 1531 w/750 sx.
DST #1 (Toronto) 4274-4310, op 90 mins, Rc 510' GIP + 210'
HCGM + 90' HG&SOCWM, ISIP 1275/30 mins, FP 60-170, FSIP
810/30 mins.
DST #2 (Lansing) 4872-4912, op 90 mins, Ga 196 MCF/30 mins,
Dec to TSTM/90 mins, Rc 1470' HCGM oil + 440' GCM, ISIP
1605/30 mins, FP 255-810, FSIP 1520/30 mins.
RTD 5910, logs to 5915. 7" @ 5910 w/200 sx. MICT.
P/44/5814-36, 48/5776-5800, 2000 AC, Rc 1d, F10d 207 BO/24 hrs,
10,000 AC, Rc 1d, F10d 20 BOPH, Set pkr @ 5740. Set BP @
4950.
P/12/4882-88, 1000-15% AC, Swb 129 BO + 162 BSW/24 hrs. PID

2732

Wintfield 2720 (+12)
C. G. 3000 (-268)
Heebner 4264 (-1532)
Toronto 4284 (-1552)
Lansing 4398 (-1666) 61 BO + 74 BXW/24 hrs - ϕ
Marmaton 5030 (-2298)
Morrow 5512 (-2780)
St. Gen 5598 (-2866)
St. Louis 5692 (-2960) ϕ 225 BOPD
TD 5915

LIBERAL TOPS

BP @ 4950, ran dual 2 3/8" I 4868 & 5740.
From St. Louis 5576-5836 IP flood 74.8 BO/8 hrs (Calc 225 BOPD), 1/4" ck, G. 380, FP 940. Complete 4/10/61.
Lansing Zone 4882-88, POP.
From 4882-88 pump 54 BO + 32 BXW/15 hrs. Later pump 65 BO + 74 BXW/24 hrs, IP 200, CP 85, G. 330/
IP Pump 61 BO + 74 BXW/24 hrs. G. 320, from Lansing 4882-88.