

JAN 18 1971



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

33-6-4111
 C NW NE

July 20, 1970

Dry/arb

COMPANY:

MATSON & THOMPSON

CONTRACTOR:

BLACKSTONE DRILLING, INC.

LEASE:

HOLBERT #1

LOCATION:

C NW NE 22-6-4

Cloud County, Kansas

Best Scanned Copy

COMPLETED:

July 10, 1970

COMPLETED:

July 19, 1970

ELEVATION:

1579 K. B.

U	to	55 55	Line	Sample Top
55	to	190 190	Shale	
190	to	250 250	Coal	Joplin 2040
250	to	265 265	Line	Keokuk 2288
265	to	510 510	Shale & Red Bed	Laranta 2310
510	to	635 635	Line & Shale	Douglas 2320
635	to	1655 1855	Shale & Line	Lansing 2416
1655	to	2540 2540	Line & Shale	BKC 2752
2540	to	2695 2695	Line	Cher 2894
2695	to	2925 2925	Line & Shale	Miss 3052
2925	to	3052 3052	Shale	G.C. 3157
3052	to	3158 3158	Mississippi	Kindershook 3219
3158	to	3219 3219	Line	Hurton 3310
3219	to	3338 3338	Shale	Mag. 3503
3338	to	3490 3490	Line	Viola 3565
3490	to	3570 3570	Line & Shale	Simpson 3747
3570	to	3760 3760	Line	Arbuckle 3869
3760	to	3779 3779	Sand	
3779	to	3807 3807	Line	
	to	3827 3827	T. D.	

Cut 12 1/4 in. hole to 265 ft. and run 268 ft. of 8 5/8 in. surface pipe, cemented with 200 sacks at 265 ft. Plug down at 5:00 P. M., July 10, 1970. Cut 7 7/8 in. hole to 3157 ft. Hole dry and abandoned. Set bottom plug at 250 ft. and filled with 25 sacks of cement. Top plug at 40 ft. and filled with 10 sacks of cement. 2 sacks in rathole. Plugged down at 12:00 Noon, July 19, 1970. Plugging completed by Gilbert Toman, State Plugger, Holyrood, Kansas.

TOPS: CERTY - 864' TARNIE - 1860' TOPEKA - 2040' LANSING - 2416'
 BAIL KANSAS CITY - 2762' CHEROKEE - 2897' MISSISSIPPI - 3052'
 KINDERSHOOK - 3219' HURTON - 3310' MAQUOKETA - 3503' VIOLA - 3565'
 DINTON - 3745' ARBUCKLE - 3869'

Measurements taken from K. B.

CERTIFICATE