

3-60

STATE Kansas	COMPANY E. K. Edmiston	
COUNTY Pratt	FARM Reed	WELL NO. 1
BLOCK	SURVEY	
SEC. 7		
T. 26	R. 15W	TOTAL DEPTH 4470
CSW-NW		
COMMENCED		
COMPLETED		
REMARKS E L		
ALTITUDE 2053		
PRODUCTION D. & A.		

CASING RECORD

DST 3902-10/1 hr. 6/15", EST 100
MCFG, 28' GCM, BHP 1390 #
DST 4327-60/1 hr. 30' M. BHP 120 #
DST 4355-85/1 hr. 6/14", 3600' WTR

SHOT QUARTS BETWEEN

FORM 186 - In stock and for sale by Ross-Martin Co., Tulsa

J. L. Chire 3/31/60

P. poor samples

Samples Start @ 3700'

samps worthless - upper hole and bed etc.

worthless from all
recive upper hole limit.

Brown Lino 3886

Lans 3900

dg platy

g + br d

bf -> w flky poorly dual col + ool on d

inter of + g fr d + soft flky ls +
dg sh - samps too poor for detail

bf -> w flky - chy ool, poorly dual ool
dg on top of ool

bf fr d, flky chy strikes
w chy ali dy - ool recive?

bf fr d on dg
inter of + g fr d + soft chy, thin
dg shales

bf ool on w chy ali dy
ool at base?

bf fr d + soft chy
blk on n + g

w chy dy ool strikes on
inter fr d + chy dy

blk on n + g
bf -> w chy dy on d

BKC 4182

thin d ls indgettable + g - g

bf -> tan fr v d + pas ali on d
inter dg + ool

bf -> tan fr d on inter d + soft chy
inter d ls + dg, g - g blk

Miss 4335

Kind 4360

mostly off w some v c, fresh, sharp

fresh + g trip +, shg +, very little sd
inter blk shale

mostly dual g sand n + blk
v c, + recive?

dg platy

Viola 4455

bf -> pk mix -> flky on v d? + may
be recive, poor samps

Total Depth 4470'

Samples to 4474'