| | |
|---|---|
| Kansas | |
| Pratt | |
| T. 29S | R. 13W |
| 14 | Luther Mackall COMPANY |
| | Thornton NO. 1 |
| | COMMENCED CE/2-SE-NW |
| | COMPLETED T.D. 4777 |
| ELEVATION 1913 | REMARKS |
| | 9-25-41 |
| PRODUCTION D.&A. | 11-1-41 |

Kraftbilt 187 ROSS-MARTIN CO. TULSA 1, OKLAHOMA PRINTED IN U.S.A.

R.K. "Kenny" Smith

100

200

300

400

500

600

700

800

900







Samples Start @ 3900′

00
04 gray-buff-brn, f-med xln, por lst
09 gray sh
brn-buff, f.xln, fos lst
34
42 gray sh
Lansing 3919
lt gray-crm, f.xln, partly chalky lst w/
gray sh breaks at base
76
~~lt gray-white-crm-brn, f.xln, partly chalky~~
~~lst w/ streaks of [illegible] por, ns~~
02 gray sh streaks
gray-crm-buff, dse-f.xln, very sl chty
lst
32
38 gray sh
50 gray-crm, f.xln, sl chty, chalky lst w/
streaks of gray sh
62 gray sh
70 buff-brn, dse lst
78 gray-crm, f.xln lst
86 crm, f.xln, ool + ooc lst; good por, ns
94 crm, f.xln, ooc, dolom, chty lst, few por
ns
02 red + gray sh
09 dk gray-gray, dse-f.xln lst
18 lt gray-crm, f.xln, sl chty, ooc lst;
good por, ns
32 gray-buff, dse-f.xln lst
lst as above w/ streaks of ooc por
58
68 lt gray, crm, f.xln lst
ns
76 gray sh
gray sh + gray-crm, f.xln lst
18
crm-buff, f.xln, sl chty lst
32
red + gray sh w/ streaks gray-crm,
52 f.xln lst
gray-crm-buff, dse lst; sl chty
73
84 gray sh
92 dk gray-buff, dse lst
lt gray-crm, f.xln lst
01
gray sh + gray-crm dse lst



-62

gray sh w/ thin streaks dse lst; chty at base

PBC 4404

-04

red & gray sh w/ tr. varic. cht

-22

-30 crm-buff-brn, dse lst

-36 sh as above

Miss. 4436

gray, opaque, sharp, blocky cht in gray

-60 dse lst; no por, no shows

-68 gray-dk grey-buff, dse lst

Kind. 4468

gray-grn & brn sh

-96

Viola 4518

gray, sl dolom sh; tr. red sh at base

-18 gray-crm, dse-f. xln, v. chty, sl dolom

-26 lst; no por, ns

-42 gray-dk gray, dse-f. xln, sl chty lst; ns

-58 lt gray, crm, med-co xln, chty lst

gray-crm, dse, chty lst

-80

-96 lt gray, f xln, dolom, v. chty lst

gray-brn, dse, sl chty lst

-12

Simpson sh 4630

lt gray, med-co. xln lst

-30

-36 gray-grn, sub waxy, v. sl sandy sh

clear, f, med & co, qz, sub rnd-sub ang, dolom sst; fair por, ns; more dolom at top

-44

Simp. sst. 4636

gray, grnish-gray sh

Arbuckle 4735

-35

gray-buff, f. xln, partly chty dolo; cht is partly ool

-55

buff, f-med xln, partly chty dolo; fair por, ns

-77

Total Depth 4777