

9-56

STATE KANSAS		COMPANY BEARDMORE & BARBARA	
COUNTY BARBER		FARM STEWART	
BLOCK		WELL NO. G12	
SEC.		SURVEY	
T. 14		TOTAL DEPTH 4913	
R. 11w		COMPLETED	
ALTITUDE 1513 RB		REMARKS SW SW SW	
PRODUCTION 130 BOPD		ELECTRIC LOG	
TDR-FL0		CASING RECORD	
DST 3579-3605 11hr 30' 6CM 60' 6CM 5pk 50			
60' H0 6CM 60' 0.14M 60' Mdy 0 Bhp 1365"			
PKR 3646			
PERF: 75/3589-3605, EST 5-10 B FPH 5% oil			
46/3578-85-30 G FPH 73 oil 1/3 wtr 100,000			
SHOT		QUARTS BETWEEN CF6	

FORM 186 - In stock and for sale by Ross-Martin Co., Tulsa

PLUG 3573 FRAC
FL0 12 B FPH 1/3 wtr 1 M L CF6:
10 B FPH, 50% wtr:
2 B 0 2 B W: 3 1/4 M CF6.

RB STEINBERG

Holding for
Sale

Sples Start 3410'

v + q sh.

gry fd
gry b f fd
gry b f fd foss. HEEBNER 3552
blk sh.
gry b f fd brn fd
gry b f fd
gry f g submicac sh.
gry f g submicac oil str sst.

gry fd
v + q sh w/ gry f g submicac
sst - spotty dk oil str -
crm gry fd foss -
v + q sdy micac sh.

streak gry b f fd lst -
-41 gry fd lst - Ls 3741
gry fd foss lst.

crm gry fd foss
crm lt gry fd faintly ool lst.
crm gry fd scat ool por.

crm lt gry fd
crm lt b f fd ay

crm gry fd
crm gry b f fd foss.
crm b f fd slay
gry b f fd faintly ool -
gry b f fd slay
gry b f fd.

gry fd
gry b f fd
dk gry to blk sh.
crm gry b f fd slay
crm gry fd ay
crm gry fd

crm b f fd ay.
crm gry fd ay

gry b f fd slay
dk gry to blk sh.
crm gry fd scat ool por.
dk gry to blk sh.

gry b f fd
crm gry fd slay
gry b f fd foss
b f to brn fd
gry b f fd
crm b f fd
crm gry fd foss.

gry b f fd
crm b f fd slay
crm b f fd.

dk gry to blk sh.
gry b f fd BURGESS Sst 4396

gry b f fd
glassy non-micac sh. in b f to sub
glassy non-micac sh. at base.
wh opg to sub opg to ss. residual
shale at top MISS 4406
lt gry to b f to med. xln ay lst.

-26 almost 100% wh sm opg to sub opg d
-38 gry b f f xln lst
-65
green & dk greenish-grey sh.
RHK SH 4565

CHATTANOOGA 4630
MISNER SET 4668
blk blocky spore-bearing sh.
VIOLA 4670

b f to cog sub brnd tight pyritic sst.
gry b f to med. xln dolomitic lst
w/ gry tan & brn opg a -

-31 gry co xln lst SM 4744
-44
-59 lvn subwaxy sl sdy sh.
wh f to cog sst to sub brnd frosted
friable sst.
dolomitic in part

-66 green subwaxy sdy sh.
ARB 4869

-69 gry b f f to co xln dolo. sl
sdyl at top.

13 TD.
sple TD 4915'

VERY "POOR SAMPLES"

EXTREMELY POOR SPLES TO 3900'