

33-10-10E


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - AMERADA PETROLEUM CORP.
Farm - Adelaide Enlow No. 1

SEC. 33 T. 10 R. 10E
SW SW SE
330' N & 330' E SWc SE

Total Depth. 2705'
Comm. 9-20-48 Comp. 10-8-48
Shot or Treated.
Contractor. Noble Drlg. Co.
Issued. 5-14-49

County. Wabaunsee
KANSAS



8-5/8" CASING:
113' Cem. w/90 sx.

Elevation. 1067 D.F.
1065 L.S.
Production. Dry D+A

Figures indicate Bottom of Formations.

lime & shale 202
lime 215
lime & shale 272
lime 315
shale 352
sand 450
shale 483
lime 510
shale 539
lime 570
sand 613
lime 648
shale 685
lime 720
sand 750
shale 797
lime & shale 823
lime 862
shale & sand 990
sand 1043
lime 1090
shale 1100
lime 1255
shale 1262
lime 1350
shale 1400
lime & shale 1515
sand & shale 1560
sand & shale & arcose 1784
lime 1790
chert 1805
lime 1822
shale 2013
dolomite 2367
shale 2397
dolomite 2415

Tops:
Topeka 539
Oread 822
Lansing K. C. 1060
Harmaton 1412
Mississippi 1784
Kinderhook 1822
Hunton 2023
Sylvan 2367
Viola 2441
Simpson 2496
Arbuckle 2671
Pre-Camb. 2690

Cored: 2398' to 2408' -
Recovered 10' greenish-gy
silty shale w/fine xlyn
dolomite.

shale 2441
dolomite 2496
lime 2545
shale 2560
lime 2580
shale & lime 2645
sand 2665
shale 2671
dolomite 2690
granite 2705
Total Depth

Ran Schlumberger to total depth
of 2705'. Schlumberger total
depth 2704'.