

14-10-14E

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **FOUR STATES OIL & GAS**

SEC. 14 T 10 R 14E
LOC C NE SE

FARM **Daniels**

NO 1

TOTAL DEPTH **3027'**

COMM. **11-25-65**

COMP. **12-6-65**


SHOT OR TREATED

CONTRACTOR **White & Ellis**

ISSUED **4-30-66**

COUNTY **Shawnee**

KANSAS



CASING

20	10 "	120'	cem w/ 60 sx
15	8		
12	6		
13	5		

ELEVATION **1080' KB**

PRODUCTION **DRY**

FIGURES INDICATE BOTTOM OF FORMATIONS

soil	5
lime	12
shells & clay	30
shells	35
black shale	75
lime brown	80
shale & shells	120
shale & lime strks	310
shale	353
lime	386
shale & lime	520
lime & shale	675
shale	945
lime	1015
shale	1043
lime	1265
shale	1353
lime	1490
shale & lime	1565
shale	2010
lime	2318
shale	2506
lime	2718
shale	2788
lime	2918
sand	2990
lime	3027
Total Depth	

Hunton	2506	2506
Maquoketa	2714	
Viola	2786	2788
St. Peter	2918	
Arbuckle	2990	2990

TOPS: S	SCOUT	LOG
Topeka	297	
Deer Creek	414	
Platts	629	
Heebner	662	
Douglas	699	
Lansing	921	
Kansas City	1042	
Cherokee	1478	
Mississippi	2098	
Kinderhook	2318	2123