


Plotted
4-10-20E

BILLINGSLEY ET AL
McLaughlin No. 1.

SEC.4 T.10 R.20 E
NE SW NW

Total Depth. 1601½'
Comm. 8-27-42 Comp. 9-20-42
Shot or Treated.
Contractor. Olie Berentz
Issued. 12-12-42

County. Jefferson



CASING:
8" 875'
6 5/8" 1417' UR 1450'

Elevation. 1091 243

Production. Est. 50 B.

Figures Indicate Bottom of Formations.

soil	10	sand	1275
sand & gravel	18	sdv shale 3BPH	1300
lime	23	shale dk	1325
shale	55	shale	1414
lime	60	gas sand filled	
shale	85	hole w/wtr	1417
lime	115	sand	1418
shale	120	shale	1425
lime	125	sand	1448
shale	135	lime	1487
lime	143	lime gas show	1490
shale	300	lime	1495
sand wtr	320	lime oil show	1498
shale	410	lime hole dry no	
lime	435	wtr	1508
shale	438	lime	1519
lime	445	lime oil show-1530	1535
shale	460	lime	1588
lime	475	lime free oil	1593½
shale	509	lime more oil	1596½
lime	519	lime 1/4 BO	1599
shale	546	lime lot of oil	1601½
lime	560	Total Depth.	
shale	575		
lime	582		
shale	590	Top lime 1447 Miss.	
lime	600	1438-1447 SIM	
shale	614	10-15-42 pmp 22 B. per day	
lime	630		
shale	640		
lime	645		
shale	650		
lime	657		
shale	663		
lime	690		
shale	694		
lime	719		
shale 8BPH 725	722		
lime	740		
shale	775		
sand	776		
shale caving	875		
shale	908		

lime	913
shale	916
lime	927
shale	950
lime	955
shale	960
lime	965
shale	1015
sand 2 BPH	1030
shale	1110
sand	1125
shale	1188
sand	1200
shale 2 BPH	1225