

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 3133
Name: KLM EXPLORATION CO. INC.
Address: 600 E. LAKE ST.
City/State/Zip: McLOUTH, KS 66054
Purchaser: EQUILON ENTERPRISES LLC
Operator Contact Person: LARRY ALEX
Phone: (913) 796-6763
Contractor: Name: KAN-DRILL INC.
License: 32548
Wellsite Geologist: LARRY ALEX

Designate Type of Completion:

☒ New Well ☐ Re-Entry ☐ Workover
☒ Oil ☐ SWD ☐ SIOW ☐ Temp. Abd.
☐ Gas ☐ ENHR ☐ SIGW
☐ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
☐ Deepening ☐ Re-perf. ☐ Conv. to Enhr./SWD
☐ Plug Back _____ Plug Back Total Depth _____
☐ Commingled _____ Docket No. _____
☐ Dual Completion _____ Docket No. _____
☐ Other (SWD or Enhr.?) _____ Docket No. _____

7-13-00 7-20-00 7.23.02
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 087-20,592
County: JEFFERSON
S2-SW-SW Sec. 8 Twp. 10 S. R. 20 ☒ East ☐ West
380 FSL feet from (S) / N (circle one) Line of Section
4630 FEL feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW (SW)
Lease Name: WAGNER Well #: 14
Field Name: McLOUTH STORAGE FIELD

Producing Formation: McLOUTH SANDSTONE
Elevation: Ground: 1096' Kelly Bushing: -
Total Depth: 1575 Plug Back Total Depth: 1573
Amount of Surface Pipe Set and Cemented at 100 FEET Feet
Multiple Stage Cementing Collar Used? ☐ Yes ☒ No
If yes, show depth set --- Feet
If Alternate II completion, cement circulated from 100 FEET
feet depth to SURFACE w/ 50 sx cmt.

Drilling Fluid Management Plan NA-11 EA B.1.02
(Data must be collected from the Reserve Pit)
Chloride content Fresh water ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ ☐ East ☐ West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Larry D. Alex
Title: Consultant Date: 6-20-01
Subscribed and sworn to before me this 20 day of 6-01
Notary Public: Herbert Edmonds
Date Commission Expires: 11-1-02
NOTARY PUBLIC
State of Kansas

KCC Office Use ONLY

NO Letter of Confidentiality Attached
If Denied, Yes ☐ Date: _____
☒ Wireline Log Received
NO Geologist Report Received
UIC Distribution _____

RECEIVED

Operator Name: KLM EXPLORATION CO. INC. Lease Name: WAGNER Well #: 14
 Sec. 8 Twp. 10 S. R. 20 ☒ East ☐ West County: JEFFERSON

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes ☒ No
 (Attach Additional Sheets)

Samples Sent to Geological Survey ☐ Yes ☒ No

Cores Taken ☐ Yes ☒ No

Electric Log Run ☒ Yes ☐ No
 (Submit Copy)

List All E. Logs Run:

DUAL COMPENSATED POROSITY LOG
 DUAL INDUCTION LOG
 SONIC BOND LOG

☒ Log Formation (Top), Depth and Datum ☐ Sample

Name Top Datum

b KANSAS CITY b 810'

McLOUTH SANDSTONE 1497' 1525'

MISSISSIPPIAN LIME 1549'

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12.25"	8.625"	24#	97'	CLASS A	50	OWC Cement
PRODUCTION	6.75"	4.5"	10.5#	1574'	50/50 poz mi	170	
					OWC cemer	50	

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
☐ Perforate				
☐ Protect Casing				
☐ Plug Back TD				
☐ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	1516 - 1528	3 1/8" HSC	1516-28

TUBING RECORD		Size 2 3/8"	Set At 1528	Packer At	Liner Run ☐ Yes ☒ No			
Date of First, Resumed Production, SWD or Enhr.			Producing Method ☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (Explain)					
Estimated Production Per 24 Hours	Oil 10	Bbls.	Gas 0	Mcf	Water 1	Bbls.	Gas-Oil Ratio	Gravity 21

Disposition of Gas

METHOD OF COMPLETION

Production Interval

☐ Vented ☐ Sold ☒ Used on Lease
 (If vented, Sumit ACO-18.)

☐ Open Hole ☒ Perf. ☐ Dually Comp. ☐ Commingled
☐ Other (Specify)