

TECHNICIAN'S PLUGGING REPORT

Operator License # 9362

Operator: William Nat'l Gas Co.

Name:

Address P.O. Box 3288

Tulsa, OK

SW4, SEC. 3, T. 10 S, R. 20 W E

2130 feet from S section line

3300 feet from E section line

Lease Name Longwell-Barkers Well # 2

County Leavenworth

Well Total Depth 1400 feet

Conductor ⁴⁵ Pipe: Size 7" feet 1377

Surface Casing: Size 10" feet 37

Abandoned Oil Well _____ Gas Well V Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Consolidated Ind Serv. License Number 31440

Address P.O. Box 884 Chanute, Ks. 66720

Company to plug at: Hour: AM Day: 30 Month: 10 Year: 19 97

Plugging proposal received from Toni Cook

(company name) Wm Nat'l Gas (phone) 216-496-7880

Work: Spot 50 ft plug at TD. 50 ft plug in & out of 7' at 500'
350 to Surf in & out of 7'.

Plugging Proposal Received by J. Robison
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: PM Day: 5 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT Spot 25 sks at TD to 950'. Perf at 700'. Set packer
at 60' and squeeze 60 sks. Cement top at 617. Perf at 500'. Set packer
at 60' and squeeze 180 sks. Remove packer and Top off with 30 sks.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

I (did) / did not observe this plugging.

Signed Jack Robison
(TECHNICIAN)