

Company Chas. T. Judd

Sec. 26 T. 10 N. 23 E

Loc. 360' W of EL, 660' N of SL

(CEL SE SE)

26-10-23E

Farm John Haff

No. 2

Total Depth 653

Comm. 3/12/31


Shot or Treated

Contractor

Issued

Comm. 3/18/31

County Wyandotte



Casing

20 in.

15 1/2

12 1/2

13 3/8

10 in.

8 1/4 6 1/4" - 460'

6 5/8

5 3/16

Elevation 974

Ruf WS tie 984

Production 277,000 cu. ft. gas

190# FP

Figures Indicate Bottom of Formation

soil & clay	26 1/2	shale dark	550
lime sandy	41	lime lex	553
shale black	46	shale dark	558
lime	50	lime sandy	565
shale gray	69	shale sticky	577
lime	83	lime	578
shale gray	111	shale black	580
lime	119	sand	582
shale blue	156	shale gray	590
lime	185	lime	593
shale blue	191	shale white	606
lime	198	lime sandy	609
shale gray	209	lime	611 Gas bubbles
lime	219	sand	615
shale gray	223	sand	653
lime	238		
shale gray	252		
lime	260		
shale gray	262		
lime	265		
shale dark gray	269		
lime	274		
slate & shale	277 Gas bubbles		
lime	297 (Winterset)		
shale dark	301		
slate black	303		
lime	321 (Bethany Falls)		
shale black	329		
lime (Hertha)	334		
shale gray	454		
red bed	459		
shale gray	464		
lime	472		
shale gray	490		
lime	494		
sand	502 Show gas		
shale gray	505		
lime hard	509		
slate black	513		
lime	519		
shale light	525		
lime	528 SLM 527		
sand	536 Gas bubbles		

Packer @ 610'

T.D.

Pave