

27-10-3E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KEWANEE OIL CO.
Farm- Clay No. 1

SEC. 27 T. 10 R. 3E
NW NW NE
330' FNL 2310' FEL

Total Depth. 3080'
Comm. 7-1-59 Comp. 7-13-59
Shot or Treated.
Contractor. Graham-Michaelis Drlg. Co.
Issued. 8-8-59

County Clay
KANSAS



CASING:
8 5/8" 279.76' w/125 sx cem.

Elevation. _____

Production. DRY

Figures indicate Bottom of Formations.

surface	0
clay, rock, shale	100
shale, gyp	274
shale, lime	1090
lime, shale	1380
shale, lime	1540
lime	1801
lime, shale	2010
lime, chert	2129
cherty dolomite	2240
shale	2360
lime, chert	2438
lime	2535
lime, chert	2580
lime, shale	2695
shale	2746
lime, shale	2810
lime	3037
shale, lime	3079 RTD
shale, lime	3080
Total Depth	

TOPS: C.M. MEAS.	SAMPLE	SCHL.
Heebner	1429	1426
Douglas	1457	1455
Brown lime	1540	1541
Lansing	1561	1563
B/Kansas City	1852	1844
Marmaton	1882	1883
Cherokee	1928	
Chat	2072	2080
Mississippi dolomite	2117	
B/Mississippi	2224	2188
Hunton	2345	2352
Maquoketa	2640	2643
Viola	2712	2710
Simpson	2860	2850
Arbuckle	2930	2936
Schist	3079	3040